

TABLE 6-2
FORT MORGAN DAILY PROGRESS REPORT - ROUND I

Gas Storage Well	FERC Class	Comp. Type	Spud Date	Approx. TOC	Ground Elevation	Surf. Csg. Depth	Gamma Ray Neutron	Downhole Video Camera	Micro Vert (MV)	Temp	Noise
# 03	OBS	T/P	08/27/54	5,136	4,347	194	11/02/06	N/A	N/A	N/A	11/02/06
# 04	I / W	C	09/13/54	?	4,351	179	10/26/06	10/28/06	10/27/06	10/27/06	10/28/06
# 06	OBS	T/P	11/10/54	?	4,351	178	N/A	N/A	N/A	N/A	N/A
#09	I / W	T/P	02/09/55	4,532	4,349	201	11/03/06	N/A	N/A	N/A	N/A
#11	I / W	T	09/04/59	?	4,352	161	11/06/06	N/A	N/A	11/06/06	11/07/06
#12	OBS	T/P	07/16/62	4,195	4,343	156	11/02/06	N/A	N/A	N/A	11/02/06
#15	OBS	C	08/10/62	3,958	4,350	198	10/29/06	10/31/06	10/30/06	10/28/06	10/30/06
#15	OBS	C	08/10/62	3,958	4,350	198	N/A	11/07/06	N/A	N/A	N/A
# 18	SWD	T/P	06/09/69	3,912	4,344	202	11/08/06	N/A	N/A	N/A	11/08/06
#20	I / W	C	06/01/71	Circ	4,345	223	10/29/06	10/30/06	10/30/06	10/29/06	NA
#23	I / W	C	06/17/71	Circ	4,343	217	11/08/06	11/09/06	11/09/06	11/08/06	11/09/06
#24	I / W	C	06/24/71	?	4,338	214	11/03/06	11/04/06	11/04/06	11/03/06	11/03/06
#25	I / W	T/P	06/05/72	Circ	4,351	214	11/07/06	N/A	N/A	N/A	N/A
#26	I / W	C	06/16/72	Circ	4,346	215	10/26/06	10/25/06	10/27/06	10/23/06	10/27/06
#27	I / W	C	06/26/72	Circ	4,345	213	11/09/06	11/10/06	11/11/06	11/09/06	11/10/06
#30	I / W	C	07/16/73	Circ	4,348	220	11/04/06	11/05/06	11/05/06	11/04/06	N/A
#33	I / W	C	08/01/73	Circ	4,347	216	11/05/06	11/06/06	11/06/06	11/05/06	11/05/06
#34	I / W	T-2-7/8"	07/15/01	Circ	4,344	312	10/31/06	N/A	N/A	10/31/06	N/A

Notes:

Completion Types: C=Casing, T=Tubing, T/P=Tubing/Packer.

I / W = Injection / Withdrawal

SWD = Salt Water Disposal

OBS = Observation well

GR/N = Gamma ray/Neutron

General Logging Plan:

For cased wells, the following logs were run:

GR/N, temperature, Vertilog, camera, and a noise log on any GR/N and temperature anomalies.

For tubing only wells, the following logs were run:

GR/N, temperature, and noise log on any GR/N and temperature anomalies.