

**Operating Standards in Regulation Applicable to the Proposed Location**

GMU 33-11A Pad (K33NW); Wells 33-13C, 33-5B, 33-4C, 33-3, 33-3D, 33-11D, 33-11, 33-11A, 33-6


1. All fired vessel and heater-treater stacks, vents, or other openings shall be equipped with screens or other appropriate equipment to prevent entry by wildlife, including migratory birds [Rule 604.b.(7).]
2. Operator shall install appropriate fencing and netting on all open pits to prevent access to pits by wildlife and migratory birds [Rule 902.a. and 902.d.]
3. Operator shall keep all disturbed areas free of all undesirable plant species designated to be noxious weeds [1003.f.]
4. During pipeline construction for trenches that are left open for more than five (5) days and are greater than five (5) feet in width, the operator shall install wildlife crossovers and escape ramps where the trench crosses well-defined game trails and at a minimum of one quarter (1/4) mile intervals where the trench parallels well-defined game trails [1203.a.(1)].
5. Operator shall treat waste water pits to control mosquitoes as outlined in Rule 1203.a.(8).
6. Operators shall install and utilize bear-proof dumpsters and trash receptacles per Rule 1204.a.(1).


**Conditions of Approval That Require Surface Owner Consent**

GMU 33-11A Pad (K33NW); Wells 33-13C, 33-5B, 33-4C, 33-3, 33-3D, 33-11D, 33-11, 33-11A, 33-6

Check yes or no for each condition listed, sign and return this document to CDOW.

Surface Owner		COA	Operator	
YES	NO		YES	NO
X		Set and Post speed limits below 20mph and caution signs on the access road where allowed by surface owners.	X	
X		Close and immediately reclaim all roads that are redundant, not used regularly, or have been abandoned to the maximum extent possible to minimize disturbance and habitat fragmentation.	X	
X		Reclaim mule deer habitat with native shrubs, grasses, and forbs appropriate to the ecological site disturbed where allowed by surface owners.	X	
	X	Gate the access road to this facility and limit public access if approved by the surface owner		X
X		Use a wildlife-appropriate fence as outlined in the <i>Landowner Guide to Wildlife Friendly Fences: How to build a fence with wildlife in mind</i> by Montana Fish, Wildlife, and Parks at this location if approved by the surface owner.	X	

  
 \_\_\_\_\_  
 Surface Owner  
 Wesley A & Juanita Brennan  
 466 Arrowhead Trail  
 Rifle, CO 81650

  
 \_\_\_\_\_  
 Operator  
 EnCana Oil & Gas (USA) Inc.  
 370 17<sup>th</sup> St., Suite 1700  
 Denver, CO 80202