

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐Refiling ☒
Sidetrack ☐

Document Number:

1690715

Plugging Bond Surety

20010102

3. Name of Operator: PETRO-CANADA RESOURCES (USA) INC

4. COGCC Operator Number: 72085

5. Address: 999 18TH ST STE 600

City: DENVER State: CO Zip: 80202-2499

6. Contact Name: SUSANMILLER Phone: (303)297-2100 Fax: (303)297-7708

Email: SUSAN.MILLER@PETRO-CANADA.COM

7. Well Name: HERGERT Well Number: 8-45

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7420

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 8 Twp: 6N Rng: 66W Meridian: 6

Latitude: 40.497890 Longitude: -104.796090

Footage at Surface: 932 FNL/FSL 1012 FEL/FWL
FSL FEL

11. Field Name: EATON Field Number: 19350

12. Ground Elevation: 4831 13. County: WELD

14. GPS Data:

Date of Measurement: 02/06/2008 PDOP Reading: 2.1 Instrument Operator's Name: M. ROBERT

15. If well is ☐ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 401

18. Distance to nearest property line: 151 19. Distance to nearest well permitted/completed in the same formation: 830

20.

LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| CODELL | CODL | 407-87 | 160 | SE4 |
| NIOBRARA | NBRR | 407-87 | 160 | SE4 |

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
6-66: SEC 8: SE/4

25. Distance to Nearest Mineral Lease Line: 932 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Weight Per Foot | Setting Depth | Sacks Cement | Cement Bottom | Cement Top |
|-------------|--------------|----------------|-----------------|---------------|--------------|---------------|------------|
| SURF | 12+1/4 | 8+5/8 | 26 | 750 | 538 | 750 | 0 |
| 1ST | 7+7/8 | 4+1/2 | 11.6 | 7,420 | 1,128 | 7,420 | 750 |

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments CONDUCTOR CASING WILL NOT BE UTILIZED. NO CHANGES TO LOCATION SINCE ORIGINAL SUBMITTAL

34. Location ID: 310660

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Y Print Name: SUSAN MILLER

Title: REGULATORY Date: 6/2/2009 Email: SUSAN.MILLER@PETRO-CA

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David & Neslin Director of COGCC Date: 8/31/2009

API NUMBER

05 123 26767 00

Permit Number: 20092595 Expiration Date: 8/31/2010

CONDITIONS OF APPROVAL, IF ANY:

Condition of Approval

| Comment | User Name | Comment Date |
|--|-----------|--------------|
| Agency | | |
| 1) PROVIDE 24 HOUR NOTICE OF MIRU TO ED BINKLEY AT 970-506-9834 OR E-MAIL AT ED.BINKLEY@STATE.CO.US 2) COMPLY WITH RULE 317.I AND PROVIDE CEMENT COVERAGE FROM TD TO A MINIMUM OF 200' ABOVE NIOBRARA AND FROM 200' BELOW SUSSEX TO 200' ABOVE SUSSEX. VERIFY COVERAGE WITH CEMENT BOND LOG. | | |
| 1) PROVIDE 24 HOUR NOTICE OF MIRU TO ED BINKLEY AT 970-506-9834 OR E-MAIL AT ED.BINKLEY@STATE.CO.US 2) COMPLY WITH RULE 317.I AND PROVIDE CEMENT COVERAGE FROM TD TO A MINIMUM OF 200' ABOVE NIOBRARA AND FROM 200' BELOW SUSSEX TO 200' ABOVE SUSSEX. VERIFY COVERAGE WITH CEMENT BOND LOG. | | 07/27/2009 |

Attachment Check List

| Att Doc Num | Name | Doc Description | Op. Check | File Size |
|-------------|----------------------|--------------------|-----------|-----------|
| 1690715 | APD ORIG & 1 COPY | LF@2060867 1690715 | Y | |
| 1690716 | WELL LOCATION PLAT | LF@2060868 1690716 | Y | |
| 1690717 | SURFACE AGRMT/SURETY | LF@2060869 1690717 | Y | |

Total Attach: 3 Files