

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

1904573

Plugging Bond Surety

20010102

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐Refiling ☒Sidetrack ☐

3. Name of Operator: PETRO-CANADA RESOURCES (USA) INC

4. COGCC Operator Number: 72085

5. Address: 999 18TH ST STE 600

City: DENVER State: CO Zip: 80202-2499

6. Contact Name: SUSANMILLER Phone: (303)297-2100 Fax: (303)297-7708

Email: SUSAN.MILLER@PETRO-CANADA.COM

7. Well Name: LINDBLAD Well Number: 25-32

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7600

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 25 Twp: 7N Rng: 67W Meridian: 6

Latitude: 40.543870 Longitude: -104.848910

Footage at Surface: 2174 FNL/FSL 715 FEL/FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4962 13. County: WELD

14. GPS Data:

Date of Measurement: 07/06/2007 PDOP Reading: 2.5 Instrument Operator's Name: J. RHOTEN

15. If well is ☐ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 198

18. Distance to nearest property line: 200 19. Distance to nearest well permitted/completed in the same formation: 887

20.

LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		80	W2SW
NIOBRARA	NBRR		80	W2SW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
7-67: SECTION 25: SW/4

25. Distance to Nearest Mineral Lease Line: 715 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	26	450	323	450	0
1ST	7+7/8	4+1/2	11.6	7,600	1,145	7,600	450

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments CONDUCTOR CASING WILL NOT BE UTILIZED. NO CHANGES TO LOCATION SINCE ORIGINAL SUBMITTAL

34. Location ID: 310760

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Y Print Name: SUSAN MILLER

Title: REGULATORY ANALYST Date: 6/2/2009 Email: SUSAN.MILLER@PETRO-CA

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David & Neslin Director of COGCC Date: 8/31/2009

API NUMBER

05 123 26940 00

Permit Number: 20092599 Expiration Date: 8/31/2010

CONDITIONS OF APPROVAL, IF ANY:

Condition of Approval

Comment	User Name	Comment Date
Agency		
1) PROVIDE 24 HOUR NOTICE OF MIRU TO ED BINKLEY AT 970-506-9834 OR E-MAIL AT ED.BINKLEY@STATE.CO.US 2) COMPLY WITH RULE 317.I AND PROVIDE CEMENT COVERAGE FROM TD TO A MINIMUM OF 200' ABOVE NIOBRARA AND FROM 200' BELOW SUSSEX TO 200' ABOVE SUSSEX. VERIFY COVERAGE WITH CEMENT BOND LOG.		
1) PROVIDE 24 HOUR NOTICE OF MIRU TO ED BINKLEY AT 970-506-9834 OR E-MAIL AT ED.BINKLEY@STATE.CO.US 2) COMPLY WITH RULE 317.I AND PROVIDE CEMENT COVERAGE FROM TD TO A MINIMUM OF 200' ABOVE NIOBRARA AND FROM 200' BELOW SUSSEX TO 200' ABOVE SUSSEX. VERIFY COVERAGE WITH CEMENT BOND LOG.		08/03/2009

Attachment Check List

Att Doc Num	Name	Doc Description	Op. Check	File Size
1904549	WELL LOCATION PLAT	LF@2060929 1904549	Y	
1904550	SURFACE AGRMT/SURETY	LF@2060930 1904550	Y	
1904573	APD ORIG & 1 COPY	LF@2060928 1904573	Y	

Total Attach: 3 Files