

ANADARKO PETROLEUM

Location: COLORADO Slot: SLOT#03 BELLA FEDERAL 23-7 (925'FSL & 1153'FEL)

Field: WELD COUNTY (ANADARKO) Well: BELLA FEDERAL 23-7

Facility: SEC.07-T3N-R66W Wellbore: BELLA FEDERAL 23-7 PWB



Well Profile Data							
Design Comment	MD (ft)	Inc (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)
Tie On	15.00	0.000	277.000	15.00	0.00	0.00	0.00
End of Tangent	900.00	0.000	277.000	900.00	0.00	0.00	0.00
End of Build (S)	2050.00	23.000	277.000	2019.36	27.75	-226.04	2.00
End of Tangent (S)	5016.68	23.000	277.000	4750.20	169.02	-1376.57	0.00
End of Drop (S)	6166.68	0.000	277.000	5869.57	196.77	-1602.61	2.00
End of Tangent	8222.11	0.000	277.000	7925.00	196.77	-1602.61	0.00

Location Information							
Facility Name				Grid East (USRT)	Grid North (USRT)	Latitude	Longitude
SEC.07-T3N-R66W				3190294.846	1331460.620	40°14'28.500"N	104°49'05.988"W
Slot		Local N (ft)	Local E (ft)	Grid East (USRT)	Grid North (USRT)	Latitude	Longitude
SLOT#03 BELLA FEDERAL 23-7 (925'FSL & 1153'FEL)		-2462.66	966.04	3191279.746	1329005.568	40°14'04.164"N	104°48'53.532"W
Rig on SLOT#03 BELLA FEDERAL 23-7 (925'FSL & 1153'FEL) (RT) to Mud line (Facility: SEC.07-T3N-R66W)						4855ft	
Mean Sea Level to Mud line (Facility: SEC.07-T3N-R66W)						0ft	
Rig on SLOT#03 BELLA FEDERAL 23-7 (925'FSL & 1153'FEL) (RT) to Mean Sea Level						4855ft	

Targets							
Name	MD (ft)	TVD (ft)	Local N (ft)	Local E (ft)	Grid East (USRT)	Grid North (USRT)	Latitude
BELLA FEDERAL 23-7 GEO TARGET 50' RADIUS (1160'FSL & 2580'FWL, REV-1)	6000.00	196.77	-1602.61	3189675.73	1329189.95	40°14'06.108"N	104°49'14.196"W
BELLA FEDERAL 23-7 HARDLINE IS 113°E OF GEO TARGET	6000.00	196.77	-1489.61	3189798.73	1329190.82	40°14'06.108"N	104°49'12.739"W

Plot reference wellpath is BELLA FEDERAL 23-7 (REV-A.0) PWP	
True vertical depths are referenced to Rig on SLOT#03 BELLA FEDERAL 23-7 (925'FSL & 1153'FEL) (RT)	Grid System: NAD83 / Lambert Colorado State Planes, Northern Zone (501), US feet
Measured depths are referenced to Rig on SLOT#03 BELLA FEDERAL 23-7 (925'FSL & 1153'FEL) (RT)	North Reference: True north
Rig on SLOT#03 BELLA FEDERAL 23-7 (925'FSL & 1153'FEL) (RT) to Mean Sea Level: 4855 feet	Scale: True distance
Mean Sea Level to Mud line (Facility: SEC.07-T3N-R66W): 0 feet	Depths are in feet
Coordinates are in feet referenced to Slot	
Created by: cookdarm on 8/14/2009	

