

Map Unit Description

Weld County, Colorado, Southern Part

THISTLE DOWN B31-20D
T5N, R65W, 6th P.M.
Sec. 31: SE/4NW/4

44 Olney loamy sand, 1 to 3 percent slopes

Setting

Elevation: 4600 to 5200 feet
Mean annual precipitation: 11 to 15 inches
Mean annual air temperature: 46 to 54 degrees F
Frost-free period: 125 to 175 days

Composition

Olney and similar soils: 85 percent
Minor components: 15 percent

Description of Olney

Setting

Landform: Plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Mixed deposit outwash

Properties and Qualities

Slope: 1 to 3 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high or high (0.60 to 2.00 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 15 percent
Gypsum maximum: 0 percent
Available water capacity: Moderate (about 6.5 inches)

Interpretive Groups

Land capability classification (irrigated): 3e
Land capability (non irrigated): 4c
Ecological site: Sandy Plains (R067BY024CO)

Typical Profile

0 to 10 inches: loamy sand
10 to 20 inches: sandy clay loam
20 to 25 inches: sandy clay loam
25 to 60 inches: fine sandy loam

Minor Components

Vona

Percent of map unit: 8 percent

Zigweid

Percent of map unit: 7 percent