

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

Document Number:

1710781

Plugging Bond Surety

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: KATESHIRLEY Phone: (281)876-6105 Fax: (281)876-2503

Email: _____

7. Well Name: JONES Well Number: 17-23A

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10358

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 17 Twp: 7S Rng: 94W Meridian: 6

Latitude: 39.436438 Longitude: -107.915523

Footage at Surface: 1712 FNL/FSL FSL 1119 FEL/FWL FWL

11. Field Name: RULISON Field Number: 75400

12. Ground Elevation: 7413 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/13/2008 PDOP Reading: 2.5 Instrument Operator's Name: JOHN RICHARDSON

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2470 FSL 1950 FEL/FWL FWL Bottom Hole: FNL/FSL 2470 FSL 1950 FEL/FWL FWL
Sec: 17 Twp: 7S Rng: 94W Sec: 17 Twp: 7S Rng: 94W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5232

18. Distance to nearest property line: 215 19. Distance to nearest well permitted/completed in the same formation: 311

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	139-73	40	NESW
WILLIAMS FORK	WMFK	139-73	40	NESW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEC 17 T7S R94W LOT3, SE1/4NW1/4, E1/2SW

25. Distance to Nearest Mineral Lease Line: 615 26. Total Acres in Lease: 147

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAP PIT

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20	16		100		100	0
SURF	12+1/4	8+5/8	24	1,500	550	1,500	0
1ST	7+7/8	4+1/2	11.6	10,358	450	10,358	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments THIS WELL IS A MULTI-WELL PAD AND IS ASSOCIATED WITH THE 17L PAD-16 WELLS TOTAL. DOE LETTER WAS SENT ON 6/4/09. TIER 2 OF PROJECT RULISON. COGCC DOE NOTICE 6-5-09.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Y Print Name: KATE SHIRLEY

Title: REG SPECIALIST Date: 6/4/2009 Email: KSHIRLEY@NOBLEENERGYI

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 9/27/2009

API NUMBER

05 045 18739 00

Permit Number: 20092316 Expiration Date: 9/26/2010

CONDITIONS OF APPROVAL, IF ANY:

Condition of Approval

Comment

Agency

PROJECT RULISON – DAVE NESLIN APPROVAL.

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

RESERVE PIT MUST BE LINED. COMPLY WITH ALL DOE OFFICE OF LEGACY MANAGEMENT REQUESTS FOR SAMPLING AND ANALYSIS OF NATURAL GAS AND OTHER MATERIALS ASSOCIATED WITH DRILLING AND PRODUCTION. CEMENT-TOP VERIFICATION BY CBL REQUIRED. OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL-SITE DURING DRILLING AND COMPLETION OPERATIONS. IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST-MANAGEMENT-PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS. FLOWBACK TO TANKS ONLY. SUBMIT A SECONDARY AND TERTIARY CONTAINMENT PLAN VIA SUNDRY NOTICE FORM 4 FOR THE TANKS. ATTN: CHRIS CANFIELD. OBTAIN APPROVAL OF THE PLAN PRIOR TO FLOWBACK. SPUD NOTICE MUST IDENTIFY IF THE WELL IS LOCATED IN TIER I OR TIER II OF THE APPROVED RULISON SAMPLING AND ANALYSIS PLAN. OPERATOR SHALL PROVIDE COMPLETE WELL-SPECIFIC EMERGENCY CONTACT INFORMATION TO THE COGCC AREA ENGINEER IN THE SPUD NOTICE PRIOR TO SPUDGING THE WELL. PRODUCED WATER FROM THIS LOCATION MAY NOT BE TRANSPORTED TO OR RE-USED AT ANOTHER LOCATION WITHOUT SPECIFIC WRITTEN APPROVAL FROM COGCC AND ONLY AFTER ANALYSIS CONFIRMS COMPLIANCE WITH THE RULISON SAP. DRILL SOLIDS AND CUTTINGS FROM THIS LOCATION MAY NOT BE TRANSPORTED TO, DISPOSED OF, OR RE-USED AT ANOTHER LOCATION WITHOUT SPECIFIC WRITTEN APPROVAL FROM COGCC AND ONLY AFTER ANALYSIS CONFIRMS COMPLIANCE WITH THE RULISON SAP. A CLOSED-LOOP MUD SYSTEM SHALL BE UTILIZED TO ENSURE CONTAINMENT OF ALL MATERIALS THAT HAVE BEEN IN CONTACT WITH DOWNHOLE STRATA AND FLUIDS. ALL CUTTINGS AND FRESH MAKE-UP WATER STORAGE PITS SHALL BE LINED TO ENSURE CONTAINMENT. CONTOUR FEATURES, FRENCH DRAINS, AND OTHER STORMWATER BMPs AS NECESSARY SHALL BE EMPLOYED TO ENSURE SITE INTEGRITY. NO INDIVIDUAL OPERATOR SHALL UTILIZE MORE THAN ONE RIG WITHIN ONE MILE OF THE PROJECT RULISON BLAST SITE AT

Attachment Check List

Att Doc Num	Name	Doc Description
1408928	ACCESS ROAD MAP	LF@2062251 1408928
1710775	WELL LOCATION PLAT	LF@2062041 1710775
1710776	ACCESS ROAD MAP	LF@2062249 1710776
1710777	SURFACE AGRMT/SURETY	LF@2062045 1710777
1710779	DEVIATED DRILLING PLAN	LF@2062044 1710779
1710780	CORRESPONDENCE	LF@2062042 1710780
1710781	APD ORIG & 1 COPY	LF@2062040 1710781
1710845	30 DAY NOTICE LETTER	LF@2062043 1710845
1712669	CORRESPONDENCE	LF@2142656 1712669

Total Attach: 9 Files