

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refilling
Sidetrack

Document Number:
1813824
Plugging Bond Surety

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY 4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000
City: DENVER State: CO Zip: 80202

6. Contact Name: GREGDAVIS Phone: (303)606-4071 Fax: (303)629-8272
Email: GREG.J.DAVIS@WILLIAMS.COM

7. Well Name: SAVAGE Well Number: RWF 341-35

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8091

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 35 Twp: 6S Rng: 94W Meridian: 6
Latitude: 39.487267 Longitude: -107.853225

Footage at Surface: 686 FNL/FSL FNL 2051 FEL/FWL FEL

11. Field Name: RULISON Field Number: 75400

12. Ground Elevation: 5442 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 04/23/2008 PDOP Reading: 6.0 Instrument Operator's Name: J. KIRKPATRICK

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 221 FNL 540 FEL 540 FEL 540 FEL 540
Bottom Hole: FNL/FSL 221 FNL 540 FEL 540 FEL 540
Sec: 35 Twp: 6S Rng: 94W Sec: 35 Twp: 6S Rng: 94W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 260

18. Distance to nearest property line: 554 19. Distance to nearest well permitted/completed in the same formation: 299

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	136-66	640	ALL

21. Mineral Ownership: Fee State Federal Indian Lease #: COC07506

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
 T6S-R94W; SEC 35: NW, E/2E/2, SWNE, NESW; SEC 36 ; LOTS 1.2.3.4; T7S-R94W; SEC1: LOTS 3,4, S/2NW; SEC 2: LOTS 1.3.4 S/2N/2, SEC 3: LOTS 1,2, S/2NE

25. Distance to Nearest Mineral Lease Line: 221 26. Total Acres in Lease: 1166

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: CLOSED LOOP/RE-USE

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	18	48	45		45	0
SURF	13+1/2	9+5/8	32.3	1,112		1,112	0
1ST	7+7/8	4+1/2	11.6	8,091		8,091	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments CLOSED LOOP. SEE WILLIAMS PRODUCTION COMPANY MASTER APD, STANDARD OPERATING PRACTICES VERSION: 4/27/06

34. Location ID: 323908

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Y Print Name: GREG DAVIS

Title: PERMITTING SUPERVISOR Date: 6/25/2009 Email: GREG.J.DAVIS@WILLIAMS.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 9/27/2009

API NUMBER: **05 045 18753 00** Permit Number: _____ Expiration Date: 9/26/2010

CONDITIONS OF APPROVAL, IF ANY: _____

Condition of Approval

Comment

Agency

NO CONDITIONS FOUND

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

CEMENT-TOP VERIFICATION BY CBL REQUIRED. THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 250 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
1711068	LOCATION PICTURES	LF@2089176 1711068
1711069	LOCATION PICTURES	LF@2089178 1711069
1711070	LOCATION PICTURES	LF@2089180 1711070
1711071	WELL LOCATION PLAT	LF@2089133 1711071
1711072	TOPO MAP	LF@2089134 1711072
1711073	SURFACE AGRMT/SURETY	LF@2089135 1711073
1711074	DEVIATED DRILLING PLAN	LF@2089136 1711074
1711075	FED. DRILLING PERMIT	LF@2089137 1711075
1711076	DRILLING PLAN	LF@2089138 1711076
1813824	APD ORIG & 1 COPY	LF@2089132 1813824

Total Attach: 10 Files