

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1757797

Plugging Bond Surety

20010124

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: CHERYLLIGHT Phone: (720)929-6461 Fax: (720)929-7461
Email: CHERYL.LIGHT@ANADARKO.COM

7. Well Name: NELSON Well Number: 4-35

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8380

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 35 Twp: 2N Rng: 68W Meridian: 6

Latitude: 40.098060 Longitude: -104.974590

Footage at Surface: 1535 FNL/FSL FNL 1483 FEL/FWL FWL

11. Field Name: SPINDLE Field Number: 77900

12. Ground Elevation: 4959 13. County: WELD

14. GPS Data:

Date of Measurement: 04/08/2009 PDOP Reading: 6.0 Instrument Operator's Name: DANIEL J. CORRIELL

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 660 FNL 660 FWL 660 FEL/FWL 660 FNL 660 FWL 660
Sec: 35 Twp: 2N Rng: 68W Sec: 3 Twp: 2N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1483

18. Distance to nearest property line: 1483 19. Distance to nearest well permitted/completed in the same formation: 820

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J SAND	JSND	232-23	320	W2
NIOBRARA/CODELL	NB-CD	407-87	80	N2NW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T2N-R68W-35: ALL

25. Distance to Nearest Mineral Lease Line: 660 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	850	595	850	0
1ST	7+7/8	4+1/2	11.6	8,380	200	8,380	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USEED. TWINNING PROPOSED NELSON 30-35

34. Location ID: 327855

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL LIGHT

Title: SR REGULATORY ANALYST Date: 7/21/2009 Email: CHERYL.LIGHT@ANADARKO.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 9/30/2009

API NUMBER

05 123 30648 00

Permit Number: _____ Expiration Date: 9/29/2010

CONDITIONS OF APPROVAL, IF ANY:

Condition of Approval

Comment

Agency

1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1757797	APD ORIG & 1 COPY	LF@2105001 1757797
1757798	WELL LOCATION PLAT	LF@2105003 1757798
1757799	TOPO MAP	LF@2105005 1757799
1757801	MULTI-WELL PLAN	LF@2105007 1757801
1757802	DEVIATED DRILLING PLAN	LF@2105011 1757802
1757803	30 DAY NOTICE LETTER	LF@2105009 1757803
1769109	SURFACE CASING CHECK	LF@2123284 1769109
1797800	LOCATION DRAWING	LF@2105034 1797800

Total Attach: 8 Files