

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400001541

Plugging Bond Surety

20010124

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: CherylLight Phone: (720)929-6461 Fax: (720)929-7461

Email: Cheryl.Light@anadarko.com

7. Well Name: MILLER Well Number: 21-33

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7752

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 33 Twp: 3N Rng: 66W Meridian: 6

Latitude: 40.184330 Longitude: -104.786660

Footage at Surface: 1590 FNL/FSL FNL 1384 FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4930 13. County: WELD

14. GPS Data:

Date of Measurement: 03/06/2009 PDOP Reading: 6.0 Instrument Operator's Name: TRAVIS KRAICH

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1000 FNL 2540 FWL FWL Bottom Hole: FNL/FSL 1000 FNL 2540 FWL FWL
Sec: 33 Twp: 3N Rng: 66W Sec: 33 Twp: 3N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1590

18. Distance to nearest property line: 57 19. Distance to nearest well permitted/completed in the same formation: 832

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara/Codell	NB-CD	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Please see attached lease

25. Distance to Nearest Mineral Lease Line: 1000 26. Total Acres in Lease: 5719

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	1,050	735	1,050	0
1ST	7+7/8	4+1/2	11.6	7,752	200	7,752	
1ST LINER							

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used; EXCEPTION LOCATION 603a(2) W/WAIVER

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cheryl Light

Title: Senior Regulatory Analyst Date: 7/23/2009 Email: Cheryl.Light@anadarko.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 10/2/2009

API NUMBER

05 123 30660 00

Permit Number: _____ Expiration Date: 10/1/2010

CONDITIONS OF APPROVAL, IF ANY:

Condition of Approval

Comment

Agency

OPERATOR MUST MEET WATER WELL TESTING REQUIREMENTS AS PER AMENDED RULE 318A.

EXCEPTION LOCATION WITH WAIVER; 603a(2).

1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1769092	SURFACE CASING CHECK	LF@2123302 1769092
400001552	30 DAY NOTICE LETTER	MILLER 21-33 NOTICE LETTER.pdf
400001553	DRILLING PLAN	Miller 21-33 Directional 04-06-09.pdf
400001554	TOPO MAP	MILLER 21-33 TOPO.pdf
400001555	WELL LOCATION PLAT	MILLER 21-33 PLAT.pdf
400001556	OIL & GAS LEASE	Lease.pdf
400001758	EXCEPTION LOC WAIVERS	MILLER 21-33 PROPERTY LINE WAIVER.pdf
400001759	MULTI-WELL PLAN	SEW PAD SEC. 33 3N66W33.pdf
400001760	SURFACE AGRMT/SURETY	MILLER 21-33 SOA.pdf
400001765	PROPOSED SPACING UNIT	MILLER 21-33 SPACING MAPS.pdf

Total Attach: 10 Files