

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1690342

Plugging Bond Surety

20050043

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: NICKCURRAN Phone: (720)876-5288 Fax: (720)876-6288  
Email: NICK.CURRAN@ENCANA.COM

7. Well Name: IONE Well Number: 8-0-8

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7976

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 8 Twp: 2N Rng: 66W Meridian: 6

Latitude: 40.159400 Longitude: -104.792250

Footage at Surface: 160 FNL/FSL FNL FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4901 13. County: WELD

14. GPS Data:

Date of Measurement: 03/11/2009 PDOP Reading: 0.3 Instrument Operator's Name: CRAIG BURKE

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 277

18. Distance to nearest property line: 160 19. Distance to nearest well permitted/completed in the same formation: 825

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407	160	GWA
J SAND	JSND		160	GWA
NIOBRARA	NBRR	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
 2N-66W: SEC 2-ALL, SEC 4-S/2, SEC 8-NE/4; SEC 10-E/2 LESS AND EXCEPT THE WELLBORES OF THE LONE 23-3 AND 13-4 WELLS.

25. Distance to Nearest Mineral Lease Line: 160 26. Total Acres in Lease: 1680

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	750	320	750	0
1ST	7+7/8	4+1/2	11.6	7,976	280	7,976	6,921
			Stage Tool	5,216	250	5,216	4,191

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: NICK CURRAN

Title: PERMITTING AGENT Date: 5/19/2009 Email: NICK.CURRAN@ENCANA.CO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 9/27/2009

#### API NUMBER

05 123 30613 00

Permit Number: 20092568 Expiration Date: 9/26/2010

CONDITIONS OF APPROVAL, IF ANY:

### **Condition of Approval**

Comment

Agency

1) PROVIDE 24 HOUR NOTICE OF MIRU TO JIM PRECUP AT 303-469-1902 OR E-MAIL AT JAMES.PRECUP@STATE.CO.US 2) COMPLY WITH RULE 317.I AND PROVIDE CEMENT COVERAGE FROM TD TO A MINIMUM OF 200' ABOVE NIOBRARA AND FROM 200' BELOW SUSSEX TO 200' ABOVE SUSSEX. VERIFY COVERAGE WITH CEMENT BOND LOG.

1) PROVIDE 24 HOUR NOTICE OF MIRU TO JIM PRECUP AT 303-469-1902 OR E-MAIL AT JAMES.PRECUP@STATE.CO.US 2) COMPLY WITH RULE 317.I AND PROVIDE CEMENT COVERAGE FROM TD TO A MINIMUM OF 200' ABOVE NIOBRARA AND FROM 200' BELOW SUSSEX TO 200' ABOVE SUSSEX. VERIFY COVERAGE WITH CEMENT BOND LOG.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
1690342	APD APPROVED	1690342.pdf
1690343	WELL LOCATION PLAT	
1690344	TOPO MAP	LF@2052882 1690344
1690345	MINERAL LEASE MAP	
1690346	30 DAY NOTICE LETTER	LF@2052883 1690346
1690348	EXCEPTION LOC REQUEST	LF@2052885 1690348
1690349	EXCEPTION LOC WAIVERS	LF@2052886 1690349
2032590	PROPOSED SPACING UNIT	LF@2052884 2032590
400007202	APD ORIG & 1 COPY	LF@2052880 400007202

Total Attach: 9 Files