

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1711939

Plugging Bond Surety

20060108

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refilling ☒

Sidetrack ☐

3. Name of Operator: ORION ENERGY PARTNERS LP

4. COGCC Operator Number: 10101

5. Address: 1675 BROADWAY STE 2000

City: DENVER State: CO Zip: 80202

6. Contact Name: STEVE J. HAHN Phone: (303)595-3030-X1 Fax: (303)595-3043

Email: GREGORY.DAVIS@WILLIAMS.COM

7. Well Name: JOLLEY Well Number: 17-39D

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8094

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 17 Twp: 6S Rng: 91W Meridian: 6

Latitude: 39.526351 Longitude: -107.578551

Footage at Surface: 2132 FNL/FSL FSL 2616 FEL/FWL FWL

11. Field Name: KOKOPELLI Field Number: 47525

12. Ground Elevation: 6198 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 02/27/2008 PDOP Reading: 2.5 Instrument Operator's Name: LAUREN VANCE

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2400 FSL 1980 FEL FEL Bottom Hole: FNL/FSL 2400 FSL 1980 FEL FEL  
Sec: 17 Twp: 6S Rng: 91W Sec: 17 Twp: 6S Rng: 91W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 219

18. Distance to nearest property line: 1506 19. Distance to nearest well permitted/completed in the same formation: 410

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	513-5	320	S2
WILLIAMS FORK	WMFK	513-4	320	S2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
MAP ATTACHED.

25. Distance to Nearest Mineral Lease Line: 650 26. Total Acres in Lease: 1040

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	16	65	60	100	60	0
SURF	11	8+5/8	32	1,000	400	1,000	0
1ST	7+7/8	4+1/2	11.6	8,094	1,100	8,094	4,000

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments SAME PAD AS THE JOLLEY 17-4D

34. Location ID: 335208

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: STEVE J. HAHN

Title: ANALYST Date: 7/24/2009 Email: GREGORY.DAVIS@WILLIAMS

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 10/15/2009

#### API NUMBER

05 045 16031 00

Permit Number: \_\_\_\_\_ Expiration Date: 10/14/2010

CONDITIONS OF APPROVAL, IF ANY:

### **Condition of Approval**

Comment

Agency

OPERATOR MUST COMPLY WITH RULE 317B.f FOR LOCATION IN 317B INTERNAL BUFFER ZONE.

24 HOUR SPUD NOTICE REQUIRED. E-MAIL: david.andrews@state.co.us GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 160 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
1637243	CORRESPONDENCE	LF@2160190 1637243
1711939	APD ORIGINAL	LF@2109729 1711939
1712592	WAIVERS	LF@2138086 1712592

Total Attach: 3 Files