

WELL NAME: SATER CC18-14  
T 4 N, R 63 W, 6th P.M.  
SECTION 18: SE/4 SW/4

## Map Unit Description

Weld County, Colorado, Southern Part

### 74 Vona loamy sand, 5 to 9 percent slopes

#### Setting

Elevation: 4600 to 5200 feet  
Mean annual precipitation: 13 to 15 inches  
Mean annual air temperature: 48 to 55 degrees F  
Frost-free period: 130 to 160 days

#### Composition

Vona and similar soils: 85 percent  
Minor components: 15 percent

#### Description of Vona

##### Setting

Landform: Plains  
Down-slope shape: Linear  
Across-slope shape: Linear  
Parent material: Eolian deposits

##### Properties and Qualities

Slope: 5 to 9 percent  
Drainage class: Well drained  
Capacity of the most limiting layer to transmit water (Ksat): High (1.98 to 6.00 in/hr)  
Frequency of flooding: None  
Frequency of ponding: None  
Calcium carbonate maximum: 15 percent  
Gypsum maximum: 0 percent  
Available water capacity: Moderate (about 6.5 inches)

##### Interpretive Groups

Land capability classification (irrigated): 6e  
Land capability (non irrigated): 6e  
Ecological site: Sandy Plains (R067BY024CO)

##### Typical Profile

0 to 6 inches: loamy sand  
6 to 28 inches: fine sandy loam  
28 to 60 inches: sandy loam

#### Minor Components

##### Valent

Percent of map unit: 10 percent

##### Remmit

Percent of map unit: 5 percent