

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☐  
Sidetrack ☐

Document Number:

1784293

Plugging Bond Surety

20090067

3. Name of Operator: WIEPKING-FULLERTON ENERGY LLC

4. COGCC Operator Number: 96340

5. Address: 4600 S DOWNING ST

City: ENGLEWOOD State: CO Zip: 80113

6. Contact Name: JACKFINCHAM Phone: (303)906-3335 Fax: (303)798-6542

Email: FINCHAM4@MSN.COM

7. Well Name: ALOHA MULA Well Number: #9

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8400

WELL LOCATION INFORMATION

10. QtrQtr: NESE Sec: 19 Twp: 10S Rng: 55W Meridian: 6

Latitude: 39.162230 Longitude: -103.586990

Footage at Surface: 1979 FNL/FSL FSL FEL/FWL 660 FEL

11. Field Name: GREAT PLAINS Field Number: 32756

12. Ground Elevation: 5212 13. County: LINCOLN

14. GPS Data:

Date of Measurement: 06/05/2009 PDOP Reading: 2.4 Instrument Operator's Name: KEITH WESTFALL

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 660

18. Distance to nearest property line: 660 19. Distance to nearest well permitted/completed in the same formation: 1570

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ARBUCKLE	ABCK			
CHEROKEE	CHRK			
LANSING	LNSNG			
MARMATION	MRTN			
MORROW	MRRW			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
SEC. 19: ALL, T10S, R55W

25. Distance to Nearest Mineral Lease Line: \_\_\_\_\_ 660 \_\_\_\_\_ 26. Total Acres in Lease: \_\_\_\_\_ 640 \_\_\_\_\_

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	300	240	300	
1ST	7+7/8	5+1/2	17	8,400	325	4,800	5,000

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JACK M FINCHAM

Title: AGENT Date: 8/31/2009 Email: FINCHAM4@MSN.COM

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 10/22/2009

#### API NUMBER

05 073 06390 00

Permit Number: \_\_\_\_\_ Expiration Date: 10/21/2010

CONDITIONS OF APPROVAL, IF ANY:

## Condition of Approval

Comment

Agency

1) Provide 24 hour notice of MIRU to Mike Leonard at 719-767-2805 or e-mail at mike.leonard@ state.co.us. 2) If production casing is set provide cement coverage to at least 200' above top potentially productive zone, and stage cement from 50' below Cheyenne to 50' above Dakota (est. 4550'-4000'). Run CBL to verify primary and stage cement jobs. 3) If well is a dry hole set the following plugs: 40 sks cement +/- 50' above the Lansing, 40 sks cement above any DST zone, 40 sks cement 50' below base of Cheyenne (est. 4550' up), 40 sks cement at top of Cheyenne (est. 4350' up), 40 sks cement 50' above top of Dakota (est. 4050' up), 50 sks cement from 50' below surface casing shoe up into surface casing, 10 sks cement in top of surface csg, cut 4 ft below GL, weld on plate, 5 sks cement in rat hole and mouse hole.

## Attachment Check List

Att Doc Num	Name	Doc Description
1784293	APD ORIGINAL	LF@2136508 1784293
1784294	WELL LOCATION PLAT	LF@2136510 1784294
1784295	TOPO MAP	LF@2136512 1784295
1784296	30 DAY NOTICE LETTER	LF@2136514 1784296
1784297	SURFACE AGRMT/SURETY	LF@2136516 1784297
1940675	SURFACE CASING CHECK	LF@2147257 1940675

Total Attach: 6 Files