

Map Unit Description

Weld County, Colorado, Southern Part

ERLICA N 35-320
Sec 34
T 5N
R 67W

61 Tassel fine sandy loam, 5 to 20 percent slopes

Setting

Elevation: 4850 to 5200 feet
Mean annual precipitation: 12 to 19 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 110 to 165 days

Composition

Tassel and similar soils: 85 percent
Minor components: 15 percent

Description of Tassel

Setting

Landform: Breaks
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Residuum weathered from sandstone

Properties and Qualities

Slope: 5 to 20 percent
Depth to restrictive feature: 10 to 20 inches to Paralithic bedrock
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low or moderately high (0.06 to 0.20 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 10 percent
Gypsum maximum: 0 percent
Available water capacity: Very low (about 2.0 inches)

Interpretive Groups

Land capability classification (irrigated): 6e
Land capability (non irrigated): 6e
Ecological site: Sandstone Breaks (R067BY056CO)

Typical Profile

0 to 11 inches: fine sandy loam
11 to 15 inches: very fine sandy loam
15 to 20 inches: weathered bedrock

Minor Components

Otero

Percent of map unit: 8 percent

Terry

Percent of map unit: 7 percent

Map Unit Description

Weld County, Colorado, Southern Part

ERLICH 85-22 D

Sec 34
T 5 N
R 67 W

16 Colby loam, 3 to 5 percent slopes

Setting

Elevation: 4850 to 5050 feet
Mean annual precipitation: 12 to 16 inches
Mean annual air temperature: 48 to 50 degrees F
Frost-free period: 135 to 155 days

Composition

Colby and similar soils: 85 percent
Minor components: 15 percent

Description of Colby

Setting

Landform: Ridges, hills
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Calcareous eolian deposits

Properties and Qualities

Slope: 3 to 5 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high or high (0.57 to 2.00 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 15 percent
Gypsum maximum: 0 percent
Available water capacity: High (about 10.6 inches)

Interpretive Groups

Land capability classification (irrigated): 3e
Land capability (non irrigated): 4e
Ecological site: Loamy Plains (R067BY002CO)

Typical Profile

0 to 7 inches: loam
7 to 60 inches: silt loam

Minor Components

Wiley

Percent of map unit: 8 percent

Keith

Percent of map unit: 7 percent