

Millage C 11-270
Township 4 North, Range 64 West, 6th P.M.

Map Unit Description *Fction 2: SESE*

Weld County, Colorado, Southern Part

41 Nunn clay loam, 0 to 1 percent slopes

Setting

Elevation: 4550 to 5150 feet
Mean annual precipitation: 12 to 18 inches
Mean annual air temperature: 46 to 54 degrees F
Frost-free period: 115 to 180 days

Composition

Nunn and similar soils: 85 percent
Minor components: 15 percent

Description of Nunn

Setting

Landform: Plains, terraces
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Mixed alluvium and/or eolian deposits

Properties and Qualities

Slope: 0 to 1 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low or moderately high (0.06 to 0.20 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 15 percent
Gypsum maximum: 0 percent
Available water capacity: High (about 9.1 inches)

Interpretive Groups

Land capability classification (irrigated): 2e
Ecological site: Clayey Plains (R067BY042CO)

Typical Profile

0 to 9 inches: clay loam
9 to 29 inches: clay loam
29 to 60 inches: sandy loam

Minor Components

Heldt

Percent of map unit: 7 percent

Dacono

Percent of map unit: 4 percent

Altvan

Percent of map unit: 4 percent

Milage C 11-27D
Township 4 North, Range 64 West, 6th PM.

Map Unit Description

Section 2: SESE

Weld County, Colorado, Southern Part

39 Nunn loam, 0 to 1 percent slopes

Setting

Elevation: 4550 to 5000 feet
Mean annual precipitation: 12 to 18 inches
Mean annual air temperature: 46 to 54 degrees F
Frost-free period: 115 to 180 days

Composition

Nunn and similar soils: 85 percent
Minor components: 15 percent

Description of Nunn

Setting

Landform: Terraces
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Mixed alluvium

Properties and Qualities

Slope: 0 to 1 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low or moderately high (0.06 to 0.20 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 15 percent
Gypsum maximum: 0 percent
Available water capacity: Moderate (about 8.9 inches)

Interpretive Groups

Land capability classification (irrigated): 2e
Ecological site: Loamy Plains (R067BY002CO)

Typical Profile

0 to 9 inches: loam
9 to 29 inches: clay loam
29 to 60 inches: sandy loam

Minor Components

Haverson

Percent of map unit: 10 percent

Heldt

Percent of map unit: 5 percent