

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400005490

Plugging Bond Surety

19880020

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: MARATHON OIL COMPANY

4. COGCC Operator Number: 53650

5. Address: 5555 SAN FELIPE

City: HOUSTON State: TX Zip: 77056

6. Contact Name: AnnaWalls Phone: (713)296-3468 Fax: (713)513-4394

Email: avwalls@marathonoil.com

7. Well Name: 697-21A Well Number: 25

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9185

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 21 Twp: 6S Rng: 97W Meridian: 6

Latitude: 39.509370 Longitude: -108.218160

Footage at Surface: 2319 FNL/FSL FNL 767 FEL/FWL FEL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 8368.7 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/12/2007 PDOP Reading: 2.0 Instrument Operator's Name: John Dolinar Lic. #18979

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1480 FNL 660 FEL 660 FEL 1480 FNL 660 FEL 660
Sec: 21 Twp: 6S Rng: 97W Sec: 21 Twp: 6S Rng: 97W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2000

18. Distance to nearest property line: 2319 19. Distance to nearest well permitted/completed in the same formation: 640

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-18	320	N/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
see attached sheet

25. Distance to Nearest Mineral Lease Line: 1480 26. Total Acres in Lease: 5325

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	20	56	100	100	100	0
SURF	14+3/4	9+5/8	36	2,000	1,000	2,000	0
1ST	8+3/4	4+1/2	11.6	9,185	675	9,185	5,500

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments No Rig on Location. The Pad is built. The Pit has been constructed. No expansion/additional surface disturbance will take place. No visible improvements within 400' of wellhead. Decrease surface casing setting depth. Surface owned by: OXY Minerals owned by: Chevron

34. Location ID: 335476

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Anna Walls

Title: Regulatory Compliance Rep Date: 9/28/2009 Email: avwalls@marathonoil.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 10/25/2009

API NUMBER

05 045 14717 00

Permit Number: _____ Expiration Date: 10/24/2010

CONDITIONS OF APPROVAL, IF ANY: _____

Condition of Approval

Comment

Agency

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. CEMENT-TOP VERIFICATION BY CBL REQUIRED. THE NEARBY HILLSIDE MUST BE MONITORED FOR ANY DAY-LIGHTING DRILLING FLUIDS THROUGHOUT THE DRILLING OF THE SURFACE-CASING INTERVAL. COMPLY WITH ALL PROVISIONS OF THE JUNE 12, 2008 NOTICE TO OPERATORS DRILLING WELLS WITHIN 3/4 MILE OF THE RIM OF THE ROAN PLATEAU IN GARFIELD COUNTY -- PIT DESIGN, CONSTRUCTION, AND MONITORING REQUIREMENTS. SEE ATTACHED NOTICE. THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400005645	30 DAY NOTICE LETTER	LF@2156691 400005645
400007327	SURFACE AGRMT/SURETY	LF@2156692 400007327
400007345	FORM 2 SUBMITTED	LF@2156693 400007345

Total Attach: 3 Files