

Map Unit Description

Weld County, Colorado, Southern Part

33 Kim loam, 3 to 5 percent slopes

Setting

Elevation: 4900 to 5250 feet
Mean annual precipitation: 13 to 17 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 125 to 150 days

Composition

Kim and similar soils: 90 percent
Minor components: 10 percent

Description of Kim

Setting

Landform: Alluvial fans, plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Mixed eolian deposits derived from sedimentary rock

Properties and Qualities

Slope: 3 to 5 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high or high (0.57 to 5.95 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 15 percent
Gypsum maximum: 0 percent
Available water capacity: Moderate (about 9.0 inches)

Interpretive Groups

Land capability classification (irrigated): 3e
Land capability (non irrigated): 4e
Ecological site: Loamy Plains (R067BY002CO)

Typical Profile

0 to 12 inches: loam
12 to 40 inches: loam
40 to 60 inches: fine sandy loam

Minor Components

Otero

Percent of map unit: 10 percent

ASHDN J33-19
TOWNSHIP 5 NORTH, RANGE 66 WEST
SECTION 33: NWNW

Map Unit Description

Weld County, Colorado, Southern Part

4 Aquolls and Aquepts, flooded

Setting

Elevation: 3600 to 4700 feet
Mean annual precipitation: 12 to 16 inches
Mean annual air temperature: 50 to 55 degrees F
Frost-free period: 100 to 165 days

Composition

Aquolls and similar soils: 55 percent
Aquepts, flooded, and similar soils: 25 percent
Minor components: 20 percent

Description of Aquolls

Setting

Landform: Drainageways, plains, depressions
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Recent alluvium

Properties and Qualities

Slope: 0 to 3 percent
Drainage class: Poorly drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low or high (0.06 to 6.00 in/hr)
Depth to water table: About 6 to 36 inches
Frequency of flooding: Frequent
Frequency of ponding: None
Calcium carbonate maximum: 10 percent
Gypsum maximum: 0 percent
Salinity maximum: Slightly saline or moderately saline (8.0 to 16.0 mmhos/cm)
Sodium adsorption ratio maximum: 5.0
Available water capacity: Low (about 4.7 inches)

Interpretive Groups

Land capability classification (irrigated): 6w
Land capability (non irrigated): 6w
Ecological site: Salt Meadow (R067BY035CO)

Typical Profile

0 to 8 inches: variable
8 to 60 inches: stratified sandy loam to clay

ASHTON J 33-19

TOWNSHIP 5 NORTH, RANGE 66 WEST

SECTION 33: NW1/4

Description of Aquepts, flooded

Setting

Landform: Stream terraces
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Recent alluvium

Properties and Qualities

Slope: 0 to 3 percent
Drainage class: Poorly drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low or high (0.06 to 6.00 in/hr)
Depth to water table: About 6 to 36 inches
Frequency of flooding: Frequent
Frequency of ponding: None
Calcium carbonate maximum: 10 percent
Gypsum maximum: 0 percent
Salinity maximum: Slightly saline or moderately saline (8.0 to 16.0 mmhos/cm)
Sodium adsorption ratio maximum: 5.0
Available water capacity: Low (about 4.7 inches)

Interpretive Groups

Land capability classification (irrigated): 6w
Land capability (non irrigated): 6w

Map Unit Description

Weld County, Colorado, Southern Part

Ecological site: Wet Meadow (R067BY038CO)

Typical Profile

0 to 8 inches: variable

8 to 60 inches: stratified sandy loam to clay

Minor Components

Thedalund

Percent of map unit: 10 percent

Haverson

Percent of map unit: 10 percent

ASHTON J33-19
TOWNSHIP 5 NORTH, RANGE 66 WEST
SECTION 33: NW NW