

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☐
Sidetrack ☐

Document Number:

1712444

Plugging Bond Surety

20070074

3. Name of Operator: LARAMIE ENERGY II, LLC

4. COGCC Operator Number: 10232

5. Address: 1512 LARIMER ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: WAYNE P.BANKERT Phone: (970)683-5419 Fax: (303)339-4399
Email: WBANKERT@LARAMIE-ENERGY.COM

7. Well Name: BEAVER CREEK RANCH Well Number: 08-13D

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9973

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 8 Twp: 7S Rng: 93W Meridian: 6

Latitude: 39.454734 Longitude: -107.805187

Footage at Surface: 697 FNL/FSL FSL 403 FEL/FWL FWL

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 7833 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 04/22/2009 PDOP Reading: 1.5 Instrument Operator's Name: GEORGE ALLEN

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 164 FSL 646 FEL/FWL FWL Bottom Hole: FNL/FSL 164 FSL 646 FEL/FWL FWL
Sec: 8 Twp: 7S Rng: 93W Sec: 8 Twp: 7S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 7656 ft

18. Distance to nearest property line: 612 ft 19. Distance to nearest well permitted/completed in the same formation: 1400 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	139-76		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
(SEC. 8 S2SW) (SEC. 18: L1, NENW, N2NE, SWNE) TWN. 7S, RNG. 93W 6TH PM

25. Distance to Nearest Mineral Lease Line: 164 ft 26. Total Acres in Lease: 280

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26+4/0	16		40	4	40	0
SURF	14+3/4	8+5/8	32	1,500	900	1,500	0
1ST	7+7/8	4+1/2	11.6	9,973	1,100	9,973	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments DRILLING WILL INCORPORATE A CLOSED MUD SYSTEM. NO VISIBLE IMPROVEMENTS WITHIN 200' OF THE WELLHEAD.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: WAYNE P. BANKERT

Title: REGULATORY Date: 8/20/2009 Email: WBANKERT@LARAMIE-ENER

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 10/29/2009

API NUMBER

05 045 18821 00

Permit Number: _____ Expiration Date: 10/28/2010

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 12 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
1289064	TOPO MAP	LF@2129081 1289064
1712444	APD ORIGINAL	LF@2128977 1712444
1712477	WELL LOCATION PLAT	LF@2128978 1712477
1712478	TOPO MAP	LF@2128979 1712478
1712479	SURFACE AGRMT/SURETY	LF@2128980 1712479
1712480	DEVIATED DRILLING PLAN	LF@2128981 1712480
1712481	DRILLING PLAN	LF@2128982 1712481
1712482	LOCATION PICTURES	LF@2129079 1712482

Total Attach: 8 Files