

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400004202

Plugging Bond Surety

20030009

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: Linda Pavelka Phone: (303)228-4064 Fax: (303)228-4286
Email: lpavelka@nobleenergyinc.com

7. Well Name: Battlement Mesa Well Number: 26-13A

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10761

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 26 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.405805 Longitude: -107.970299

Footage at Surface: 1793 FNL/FSL FSL 1059 FEL/FWL FWL

11. Field Name: Rulison Field Number: 75400

12. Ground Elevation: 8990 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 10/15/2007 PDOP Reading: 2.1 Instrument Operator's Name: Robert Wood

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2642 FSL 614 FWL FWL Bottom Hole: FNL/FSL 2642 FSL 614 FWL FWL
Sec: 26 Twp: 7S Rng: 95W Sec: 26 Twp: 7S Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 4825 ft

18. Distance to nearest property line: 2094 ft 19. Distance to nearest well permitted/completed in the same formation: 310 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	139-53	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Please see attached map (previously submitted)

25. Distance to Nearest Mineral Lease Line: 1500 ft 26. Total Acres in Lease: 2687

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: RE-USED THEN DISPOSAL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20+0	16	line pipe	60	100	60	0
SURF	13+1/2	9+5/8	36#	3,300	1,750	3,300	0
3RD	7+7/8	4+1/2	11.6#	10,761	1,165	10,761	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments I certify that conditions from original permit are still the same. There has been no change to land use or well construction. Pad site is built; no new disturbance. Updated 305 letter attached. Prod.String TOC=200'above WMFK. Parasite String 3,000'. Noble owns surface & minerals. Tier II of Project Rulison-DOE Notified 9/16/2009.

34. Location ID: 334415

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Linda Pavelka

Title: Regulatory Manager Date: 9/16/2009 Email: lpavelka@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 10/31/2009

API NUMBER

05 045 16078 00

Permit Number: _____ Expiration Date: 10/30/2010

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

PERFORM A HIGH-ACCURACY GYROSCOPIC DIRECTIONAL WELLBORE SURVEY UPON REACHING TOTAL DEPTH OF THE WELL. E-MAIL A COPY OF THE SURVEY ALONG WITH A SUNDRY NOTICE, FORM 4, REQUESTING APPROVAL TO DAVID.ANDREWS@STATE.CO.US THE DIRECTIONAL DRILLING SURVEY REPORT SHALL INCLUDE A MAP VIEW AND A VERTICAL PROFILE VIEW SHOWING WELLBORE TRAJECTORY AND DISTANCE FROM THE ½-MILE RADIUS FROM PROJECT RULISON. THE OPERATOR SHALL OBTAIN APPROVAL FROM THE COGCC PRIOR TO COMMENCING CASING-PERFORATING AND OTHER COMPLETION OPERATIONS. COMPLY WITH ALL DOE OFFICE OF LEGACY MANAGEMENT REQUESTS FOR SAMPLING AND ANALYSIS OF NATURAL GAS AND OTHER MATERIALS ASSOCIATED WITH DRILLING AND PRODUCTION.

CEMENT-TOP VERIFICATION BY CBL REQUIRED. FLOWBACK TO TANKS ONLY. SUBMIT A SECONDARY AND TERTIARY CONTAINMENT PLAN VIA SUNDRY NOTICE FORM 4 FOR THE TANKS. ATTN: CHRIS CANFIELD. OBTAIN APPROVAL OF THE PLAN PRIOR TO FLOWBACK. SPUD NOTICE MUST IDENTIFY IF THE WELL IS LOCATED IN TIER I OR TIER II OF THE APPROVED RULISON SAMPLING AND ANALYSIS PLAN. OPERATOR SHALL PROVIDE COMPLETE WELL-SPECIFIC EMERGENCY CONTACT INFORMATION TO THE COGCC AREA ENGINEER IN THE SPUD NOTICE PRIOR TO SPUDDING THE WELL. PRODUCED WATER FROM THIS LOCATION MAY NOT BE TRANSPORTED TO OR RE-USED AT ANOTHER LOCATION WITHOUT SPECIFIC WRITTEN APPROVAL FROM COGCC AND ONLY AFTER ANALYSIS CONFIRMS COMPLIANCE WITH THE RULISON SAP. DRILL SOLIDS AND CUTTINGS FROM THIS LOCATION MAY NOT BE TRANSPORTED TO, DISPOSED OF, OR RE-USED AT ANOTHER LOCATION WITHOUT SPECIFIC WRITTEN APPROVAL FROM COGCC AND ONLY AFTER ANALYSIS CONFIRMS COMPLIANCE WITH THE RULISON SAP.

A CLOSED-LOOP MUD SYSTEM SHALL BE UTILIZED TO ENSURE CONTAINMENT OF ALL MATERIALS THAT HAVE BEEN IN CONTACT WITH DOWNHOLE STRATA AND FLUIDS. ALL CUTTINGS AND FRESH MAKE-UP WATER STORAGE PITS SHALL BE LINED TO ENSURE CONTAINMENT. CONTOUR FEATURES, FRENCH DRAINS, AND OTHER STORMWATER BMPs AS NECESSARY SHALL BE EMPLOYED TO ENSURE SITE INTEGRITY. NO INDIVIDUAL OPERATOR SHALL UTILIZE MORE THAN ONE RIG WITHIN ONE MILE OF THE PROJECT RULISON BLAST SITE AT ANY GIVEN TIME AND NO INDIVIDUAL OPERATOR SHALL UTILIZE MORE THAN TWO RIGS WITHIN A THREE MILE RADIUS OF THE SITE AT ANY GIVEN TIME. THE TOTAL NUMBER OF RIGS ALLOWED BY ALL OPERATORS WITHIN THREE MILES OF THE SITE SHALL BE LIMITED TO FIVE AT ANY GIVEN TIME. OPERATOR SHALL COMPLY WITH ALL PROVISIONS OF THE MOST RECENT COGCC-APPROVED REVISION OF THE RULISON SAMPLING AND ANALYSIS PLAN. IN ADDITION TO THE PRODUCED-WATER SAMPLING AND ANALYSIS OUTLINED IN SECTION 5.8 OF THE PLAN, THE OPERATOR SHALL ALSO OBTAIN AND ANALYZE PRODUCED-WATER SAMPLES ON WELLS DESCRIBED IN THE PLAN FOR CONSTITUENTS LISTED IN THE PLAN USING THE SPECIFIC METHOD WHERE APPLICABLE. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 025 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
1637574	CORRESPONDENCE	LF@2170799 1637574
1712982	CORRESPONDENCE	LF@2155530 1712982
400004207	30 DAY NOTICE LETTER	LF@2152070 400004207
400005510	OTHER	LF@2152071 400005510

Total Attach: 4 Files