

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
1691686
Plugging Bond Surety
20030009

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202

6. Contact Name: MARICLARK Phone: (303)228-4413 Fax: (303)228-4286
Email: MCLARK@NOBLEENERGYINC.COM

7. Well Name: TREBOR B Well Number: 11-22

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 6900

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 11 Twp: 5N Rng: 64W Meridian: 6
Latitude: 40.414300 Longitude: -104.512390

Footage at Surface: 2940 FNL/FSL FNL 1189 FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4601 13. County: WELD

14. GPS Data:

Date of Measurement: 06/15/2009 PDOP Reading: 1.4 Instrument Operator's Name: ROBERT DALEY

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 175 ft

18. Distance to nearest property line: 174 ft 19. Distance to nearest well permitted/completed in the same formation: 773 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED

25. Distance to Nearest Mineral Lease Line: 174 ft 26. Total Acres in Lease: 242

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite
Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	500	212	500	0
1ST	7+7/8	4+1/2	11.6	6,900	607	6,900	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARI CLARK

Title: REG ANALYST II Date: 8/7/2009 Email: MCLARK@NOBLEENERGYIN

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 11/3/2009

API NUMBER
05 123 30733 00

Permit Number: _____ Expiration Date: 11/2/2010

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hr notice of spud to Ed Binkley at 970-506-9834 or e-mail at ed.binkley@state.co.us . 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 4) If dry hole, 40 sks cement 50' above Niobrara top, 50 sks cement ½ out, ½ in surface casing, 10 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole 5 sks cement in mouse hole. Restore surface location.

RIG HEIGHT CANNOT EXCEED 116 FEET (PUBLIC ROAD 175' SOUTH)

Attachment Check List

Att Doc Num	Name	Doc Description
1691686	APD ORIGINAL	LF@2120191 1691686
1691687	WELL LOCATION PLAT	LF@2120193 1691687
1691688	OIL & GAS LEASE	LF@2120195 1691688
1691689	SURFACE AGRMT/SURETY	LF@2120197 1691689
1691690	SURFACE AGRMT/SURETY	LF@2120246 1691690
1691691	30 DAY NOTICE LETTER	LF@2120199 1691691
1691692	EXCEPTION LOC REQUEST	LF@2120201 1691692
1691693	PROPOSED SPACING UNIT	LF@2120203 1691693
1940943	SURFACE CASING CHECK	LF@2162518 1940943

Total Attach: 9 Files