

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☒

Sidetrack ☐

Document Number:

1790662

Plugging Bond Surety

20090069

3. Name of Operator: DELTA PETROLEUM CORPORATION

4. COGCC Operator Number: 16800

5. Address: 370 17TH ST STE 4300

City: DENVER State: CO Zip: 80202

6. Contact Name: MIKESTANLEY Phone: (303)820-4024 Fax: (303)820-4025

Email: CJOHNSON@DELTAPETRO.COM

7. Well Name: NVEGA Well Number: 22-424

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8494

WELL LOCATION INFORMATION

10. QtrQtr: NESE Sec: 22 Twp: 9S Rng: 93W Meridian: 6

Latitude: 39.260431 Longitude: -107.749331

Footage at Surface: 1941 FNL/FSL FSL 715 FEL/FWL FEL

11. Field Name: BUZZARD CREEK Field Number: 9500

12. Ground Elevation: 7620 13. County: MESA

14. GPS Data:

Date of Measurement: 10/03/2008 PDOP Reading: 2.1 Instrument Operator's Name: SCOTT VERNON, UINTAH

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2290 FNL 330 FEL FEL Bottom Hole: FNL/FSL 2290 FNL 330 FEL FEL
Sec: 22 Twp: 9S Rng: 93W Sec: 22 Twp: 9S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 943 ft

18. Distance to nearest property line: 597 ft 19. Distance to nearest well permitted/completed in the same formation: 326 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
MESAVERDE	MVRD	399-6	160	S2N2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED.

25. Distance to Nearest Mineral Lease Line: 275 ft 26. Total Acres in Lease: 797

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: RECLAIMWATER&BURYCU

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	16	55	60	200	60	0
SURF	12+1/4	8+5/8	32	2,200	845	2,200	0
1ST	7+7/8	4+1/2	11.6	8,494	529	8,494	5,516

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments DRILLING PLAN MODIFIED TO REFLECT CEMENT TOP AT 500' OVER TOG. THE WELL LOCATION WAS BUILT 09/08 BUT IS NOT ACTIVELY BEING DRILLED AT THIS TIME. DELTA PETROLEUM CORP IS THE SURFACE OWNER AS OF 4/18/08. SURFACE LOC PER SUNDRY APPROVED 2-12-09.

34. Location ID: 334464

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL JOHNSON

Title: REGULATORY Date: 10/1/2009 Email: CJOHNSON@DELTAPETRO.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/4/2009

API NUMBER

05 077 09705 00

Permit Number: _____ Expiration Date: 11/3/2010

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us CEMENT-TOP VERIFICATION BY CBL REQUIRED. THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 210 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
1790662	APD APPROVED	1790662.pdf
1790663	WELL LOCATION PLAT	LF@2155156 1790663
1790664	TOPO MAP	LF@2155158 1790664
2097409	LEGAL/LEASE DESC	LF@2155157 2097409
400007867	FORM 2 SUBMITTED	LF@2159591 400007867
400015825	APD ORIGINAL	LF@2155155 400015825

Total Attach: 6 Files