

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1758724

Plugging Bond Surety

20010102

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: PETRO-CANADA RESOURCES (USA) INC

4. COGCC Operator Number: 72085

5. Address: 999 18TH ST STE 600

City: DENVER State: CO Zip: 80202-2499

6. Contact Name: JANKIJIWARA Phone: (303)297-2300 Fax: (303)297-7708

Email: JKAJIWARA@SUNCOR.COM

7. Well Name: EVERITT Well Number: 1160-21-32

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8000

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 21 Twp: 11N Rng: 60W Meridian: 6

Latitude: 40.905740 Longitude: -104.103660

Footage at Surface: 2213 FNL/FSL FSL 601 FEL/FWL FWL

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 5460 13. County: WELD

14. GPS Data:

Date of Measurement: 08/19/2009 PDOP Reading: 1.2 Instrument Operator's Name: BEN ADSIT

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 401 ft

18. Distance to nearest property line: 601 ft 19. Distance to nearest well permitted/completed in the same formation: 4468 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
DAKOTA	DKTA		40	NWSW
J SAND	JSND		40	NWSW
NIOBRARA-CODELL	NB-CD		40	NWSW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20010103

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T11N, R60W, SEC. 21 N/2, SW/4

25. Distance to Nearest Mineral Lease Line: 601 ft 26. Total Acres in Lease: 480

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	26	400	230	400	0
1ST	7+7/8	5+1/2	17	8,000	1,105	8,000	350

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments CONDUCTOR CASING WILL NOT BE UTILIZED

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JAN KAJIWARA

Title: REG ANALYST Date: 8/28/2009 Email: JKAJIWARA@SUNCOR.COM

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/17/2009

API NUMBER

05 123 30761 00

Permit Number: _____ Expiration Date: 11/16/2010

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Note surface casing setting depth change from 400' to 610'. Increase cement coverage accordingly and cement to surface. Set surface casing per Rule 317d, setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 2) Provide 24 hr notice of spud to Colby Horton at 970-467-2517 or e-mail at colby.horton @state.co.us . 3) If completed, cement coverage shall be at a minimum from the TD to 200' above Niobrara and at minimum set stage cement from 1210' to 50' above the surface casing shoe. Verify all placed cement with cement bond log and cementing tickets. 4) If dry hole, set 60 sks cement from 50' below D Sand base to 100' above D Sand top, 40 sks cement 50' above Niobrara top, 40 sks cement 1300', 50 sks cement ½ out, ½ in surface casing, 10 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole 5 sks cement in mouse hole. Restore surface location.

Attachment Check List

Att Doc Num	Name	Doc Description
1758724	APD ORIGINAL	LF@2135016 1758724
1758726	WELL LOCATION PLAT	LF@2135018 1758726
1758727	TOPO MAP	LF@2135020 1758727
1758728	30 DAY NOTICE LETTER	LF@2135022 1758728
1940963	SURFACE CASING CHECK	LF@2164310 1940963

Total Attach: 5 Files