

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1692505

Plugging Bond Surety

20060159

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☒

Sidetrack ☐

3. Name of Operator: BLACK RAVEN ENERGY INC

4. COGCC Operator Number: 10203

5. Address: 1125 17TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: JANICEALDSTADT Phone: (303)308-1330 13 Fax: (303)308-1590

Email: JALDSTADT@PRBENERGY.COM

7. Well Name: BRINKEMA Well Number: 943-32-21

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 3000

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 32 Twp: 9N Rng: 43W Meridian: 6

Latitude: 40.717330 Longitude: -102.161150

Footage at Surface: 900 FNL/FSL FNL 2600 FEL/FWL FWL

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 3670 13. County: PHILLIPS

14. GPS Data:

Date of Measurement: 07/27/2007 PDOP Reading: 3.2 Instrument Operator's Name: NEAL MCCORMICK

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 900 ft

18. Distance to nearest property line: 900 ft 19. Distance to nearest well permitted/completed in the same formation: 1747 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
N/2 SEC. 32 T9N R43W

25. Distance to Nearest Mineral Lease Line: 900 ft 26. Total Acres in Lease: 320

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAPORATION & BURIAL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	9+7/8	7	17	450	180	450	0
1ST	6+1/4	4+1/2	10.5	3,000	80	300	1,900

32. BOP Equipment Type: ☐ Annular Preventer ☐ Double Ram ☐ Rotating Head ☒ None

33. Comments NO CONDUCTOR CASING WILL BE USED. WELL NAME WAS CHANGED FROM BRINKEMA FARMS 943-32-21 TO BRINKEMA 943-32-21. NOTHING ON THE SURFACE HAS CHANGED SINCE THE ORIGINAL APD WAS SUBMITTED AND APPROVED UNDER API #05-095-06161-00.

34. Location ID: 314070

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JANICE ALDSTADT

Title: LANDMAN Date: 10/22/2009 Email: JALDSTADT@PRBENERGY.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/20/2009

#### API NUMBER

05 095 06161 00

Permit Number: \_\_\_\_\_ Expiration Date: 11/19/2010

CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

1. Provide 24 hr notice of spud to Colby Horton at 970-467-2517 or colby.horton@state.co.us. 2. Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3. If completed, provide cement coverage from TD to 200' above Niobrara. Verify coverage with cement bond log. 4. If well is a dry hole set the following plugs: a) 35 sks cement from 50' above Niobrara top up, b) 35 sks cement ½ out, ½ in surface casing c) 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole and 5 sks cement in mouse hole. Restore surface location.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
1303754	SURFACE CASING CHECK	LF@2178820 1303754
1692505	APD ORIGINAL	LF@2163487 1692505
1692507	30 DAY NOTICE LETTER	LF@2163489 1692507
1692513	WELL LOCATION PLAT	LF@2163491 1692513
1692514	TOPO MAP	LF@2163493 1692514
400011158	FORM 2 SUBMITTED	LF@2170373 400011158

Total Attach: 6 Files