

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐
Refiling ☒Sidetrack ☐

Document Number:

400017992

Plugging Bond Surety

20020067

3. Name of Operator: ENCANA OIL &amp; GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Julia Carter Phone: (720)876.5240 Fax: (720)876.6240

Email: Julia.Carter@encana.com

7. Well Name: N. Parachute Well Number: EF16B-19 C29 59

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 12767

## WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 29 Twp: 5S Rng: 95W Meridian: 6

Latitude: 39.590392 Longitude: -108.080414

 Footage at Surface: 609 FNL/FSL 1971 FEL/FWL  
 FNL FWL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 7011 13. County: GARFIELD

## 14. GPS Data:

Date of Measurement: 11/02/2007 PDOP Reading: 2.4 Instrument Operator's Name: Robert Kay

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.
 Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
 975 FSL 658 FEL 975 FSL 658 FEL  
 Sec: 19 Twp: 5S Rng: 95W Sec: 19 Twp: 5S Rng: 95W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 9240 ft

18. Distance to nearest property line: 7233 ft 19. Distance to nearest well permitted/completed in the same formation: 330 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	479-15		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer): \_\_\_\_\_

25. Distance to Nearest Mineral Lease Line: 3323 ft 26. Total Acres in Lease: 25889

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Recycle & Bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	20	Line Pipe	90	6	90	
SURF	12+1/4	9+5/8	36	2,800	1,646	2,800	
2ND	7+7/8	4+1/2	11.6	12,767	1,124	12,767	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments EnCana Oil & Gas (USA) Inc. owns surface, EnCana minerals. The full well number is EF16B-19 C29 595. This is a Refile. API # 05-045-15595. This location has been built and no further surface disturbance will occur, therefore a Form 2A will not be submitted. There have been no changes to the well plan, surface conditions or lease terms. Please note the surface casing hole size will be both 12-1/4" and 14-3/4". The second string, or production casing, hole size will be both 7-7/8" and 8-3/4" with its cement top at 200' above WMFK. Cement top for both conductor and surface casing will be run to surface.

34. Location ID: 335692

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Julia M. Carter

Title: Regulatory Analyst Date: \_\_\_\_\_ Email: Julia.Carter@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

**API NUMBER**

05 045 15595 00

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.