

## Kubeczko, Dave

---

**To:** Kubeczko, Dave  
**Subject:** FW: Pioneer Natural Resources, Stage Coach 42-26 TR, SENE Sec 26 T33S R67W, Las Animas County, Form 2A (#400014628) Review

Scan No 2032713      CORRESPONDENCE      2A#400014628

---

**From:** Kovacik, Georgina [mailto:Georgina.Kovacik@pxd.com]  
**Sent:** Friday, December 18, 2009 9:31 AM  
**To:** Kubeczko, Dave  
**Subject:** RE: Pioneer Natural Resources, Stage Coach 42-26 TR, SENE Sec 26 T33S R67W, Las Animas County, Form 2A (#400014628) Review

Hi Dave,

1. Please change the size of the disturbed area after reclamation to 0.5 acre.
2. Please also change the static water level to 65 ft and to sensitive area. The COA's are ok.

Thanks,

Georgina Kovacik  
PNR

---

**From:** Kubeczko, Dave [mailto:Dave.Kubeczko@state.co.us]  
**Sent:** Wednesday, December 09, 2009 5:49 PM  
**To:** Kovacik, Georgina  
**Subject:** Pioneer Natural Resources, Stage Coach 42-26 TR, SENE Sec 26 T33S R67W, Las Animas County, Form 2A (#400014628) Review

Georgina,

I have been reviewing the Stage Coach 42-26 TR **Form 2A** (#400014628). COGCC requests the following clarifications regarding the data Pioneer has submitted on or attached to the Form 2A prior to passing the Oil and Gas Location Assessment.

1. **Construction (Section 6):** The size of the disturbed area during construction (1.00 acres) and size of location after interim reclamation (1.00 acres) are the same. I would think that after interim reclamation, the disturbed area would be less. Can you please confirm what these sizes are. I can make the change if you send an email with this request.
2. **Water Resources (Section 14):** Form 2A indicates that the distance to the nearest surface water is 156 feet. Form 2A also indicates the depth to groundwater to be 200 feet bgs for a well located 2804 feet from the proposed well. COGCC's review indicates there is a water well (Permit No. 272533-Chenoweth, domestic well) to the southwest, with a total depth of 200 feet bgs and a depth to groundwater of 65 feet bgs. I believe this is the well you located. The number that comes up on our GIS map is 200 feet (this number often pertains to the total depth of the well, not the depth to groundwater). I can make the change if you send me an email with this request. COGCC guidelines require designating all locations with close proximity to surface water (i.e., less than 500 feet) a **sensitive area** and requiring the following conditions of approval (COAs):  
**COA 4** - Location is in a sensitive area because of close proximity to surface water, therefore, operator must ensure 110 percent secondary containment for any volume of fluids contained at well site during drilling and completion operations.

**COA 5** - Operator must implement best management practices to contain any unintentional release of fluids.

COGCC would appreciate your concurrence with attaching these COAs to the Form 2A permit prior to passing the OGLA review. The other issues are very minor and I would like to get this passed. If you have any questions, please do not hesitate to call me at (970) 625-2497 x5 (office) or (970) 309-2514 (cell), or email. Thanks.

Dave

**David A. Kubeczko, PG**  
**Oil and Gas Location Assessment Specialist**

Colorado Oil & Gas Conservation Commission  
Northwest Area Office  
707 Wapiti Court, Suite 204  
Rifle, CO 81650  
Phone: (970) 625-2497x5  
FAX: (970) 625-5682  
Cell: (970) 309-2514  
[dave.kubeczko@state.co.us](mailto:dave.kubeczko@state.co.us)



 *Please consider the environment before printing this e-mail*

Statement of Confidentiality:

This message may contain information that is privileged or confidential. If you receive this transmission in error, please notify the sender by reply e-mail and delete the message and any attachments.