

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1791401

Plugging Bond Surety

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER _____
 SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒
Refiling ☒Sidetrack ☐3. Name of Operator: EXXON MOBIL OIL CORPORATION4. COGCC Operator Number: 287005. Address: P O BOX 4358 WGR RM 310City: HOUSTON State: TX Zip: 77210-43586. Contact Name: MARK DEL PICO Phone: (281)654-1926 Fax: (281)654-1940Email: MARK.DELPICO@EXXONMOBIL.COM7. Well Name: PICEANCE CREEK UNIT Well Number: 197-36A58. Unit Name (if appl): PICEANCE CREEK Unit Number: COC-47666X9. Proposed Total Measured Depth: 14

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 36 Twp: 1S Rng: 97W Meridian: 6Latitude: 39.918617 Longitude: -108.229133
 Footage at Surface: 1849 FNL/FSL FSL 2613 FEL/FWL FWL
11. Field Name: PICEANCE CREEK Field Number: 6880012. Ground Elevation: 7082 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 09/12/2007 PDOP Reading: 2.4 Instrument Operator's Name: T. PETTY15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL 1767 FSL 2586 FWL FWL Bottom Hole: FNL/FSL 1767 FSL 2586 FWL FWL
 Sec: 36 Twp: 1S Rng: 97W Sec: 36 Twp: 1S Rng: 97W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☐ No17. Distance to the nearest building, public road, above ground utility or railroad: 200 ft18. Distance to nearest property line: 9142 ft 19. Distance to nearest well permitted/completed in the same formation: 933 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
MESAVERDE	MVRD			
OHIO CREEK	OHCRK			
WASATCH	WSTC			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC035729

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

25. Distance to Nearest Mineral Lease Line: 8131 ft 26. Total Acres in Lease: 1869

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: BURIAL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20	16	LINEPIPE	120	90	120	0
SURF	14+3/4	10+3/4	45.5	4,700	2,400	4,700	0
1ST	9+7/8	7	26	9,800	1,510	9,800	4,400
2ND	6+1/8	4+1/2	15.1	14,100	640		7,500

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☒ None

33. Comments THIS APD EXPIRES ON 2/18/2010. NO CHANGE TO APPROVED APD. THIS PAD HAS BEEN BUILT & CONDUCTOR/CELLARS HAVE BEEN SET FOR ALL 10 WELLS ON THIS PAD. NO FORM 2A IS REQUIRED AS THIS IS NOT IN A RSO AREA. API #05-103-11184-00.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARK DEL PICO

Title: REGULATORY Date: _____ Email: MARK.DELPICO@EXXONMO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Permit Number: _____ Expiration Date: _____

API NUMBER

05 103 11184 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
1791401	APD ORIGINAL	LF@2197492 1791401

Total Attach: 1 Files