

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
400009896
Plugging Bond Surety
20040071

3. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION 4. COGCC Operator Number: 10079

5. Address: 1625 17TH ST STE 300
City: DENVER State: CO Zip: 80202

6. Contact Name: Hannah Knopping Phone: (303)357-6412 Fax: (303)357-7315
Email: hknopping@anteroresources.com

7. Well Name: Robinson Well Number: C8

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8719

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 17 Twp: 6S Rng: 92W Meridian: 6
Latitude: 39.527193 Longitude: -107.682521

Footage at Surface: 2464 FNL/FSL FNL 365 FEL/FWL FEL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 5639 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 01/19/2007 PDOP Reading: 1.2 Instrument Operator's Name: Scott E. Aibner

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
2495 FSL 725 FEL 2495 FSL 725 FEL
Sec: 17 Twp: 6S Rng: 92W Sec: 17 Twp: 6S Rng: 92W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 531 ft

18. Distance to nearest property line: 205 ft 19. Distance to nearest well permitted/completed in the same formation: 324 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	191-25	320	S/2
Williams Fork	WMFK	191-24	320	S/2

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See Exhibit A -Sec 17 -E/2NWNW, E/2NW, SWNE, E/2SW, SE/4 (previously submitted)

25. Distance to Nearest Mineral Lease Line: 177 ft 26. Total Acres in Lease: 374

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: Closed Loop: Grfld Cty Lndfl

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	16	55#	50	148	50	0
1ST	12+1/4	8+5/8	24#	900	381	900	0
2ND	7+7/8	5+1/2	17#	8,719	821	8,719	4,179

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments I certify that all conditions in the original permit are the same. No changes to land use, well construction, or lease. Pad is built. No expansion or additional disturbance will occur. Closed Loop system will be used.

34. Location ID: 335546

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Hannah Knopping

Title: Permit Representative Date: 10/19/2009 Email: hknopping@anteroresources.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 12/18/2009

API NUMBER
05 045 17107 00

Permit Number: _____ Expiration Date: 12/17/2010

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 300 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400010646	30 DAY NOTICE LETTER	LF@2175607 400010646
400010647	WAIVERS	LF@2175608 400010647
400010648	FORM 2 SUBMITTED	LF@2175609 400010648

Total Attach: 3 Files