

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400010972

Plugging Bond Surety

20040071

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION

4. COGCC Operator Number: 10079

5. Address: 1625 17TH ST STE 300

City: DENVER State: CO Zip: 80202

6. Contact Name: Ashlie Mihalcin Phone: (303)357-7323 Fax: (303)357-7315

Email: amihalcin@anteroresources.com

7. Well Name: North Bank Well Number: B7

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 9052

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 12 Twp: 6S Rng: 93W Meridian: 6

Latitude: 39.544640 Longitude: -107.717108

Footage at Surface: 1297 FNL/FSL FNL 538 FEL/FWL FEL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 5413 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 03/21/2006 PDOP Reading: 2.2 Instrument Operator's Name: Samuel D. Phelps

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1168 FNL 220 FWL FWL Bottom Hole: FNL/FSL 1168 FNL 220 FWL FWL  
Sec: 7 Twp: 6S Rng: 92W Sec: 7 Twp: 6S Rng: 92W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 229 ft

18. Distance to nearest property line: 154 ft 19. Distance to nearest well permitted/completed in the same formation: 399 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	191-25		
Williams Fork	WMFK	510-16		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20040072

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
Lease plat and description attached to original permit application.

25. Distance to Nearest Mineral Lease Line: 220 ft 26. Total Acres in Lease: 70

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Closed Loop/Grfld Cty Lndfl

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	16	55#	50	148	50	0
SURF	12+1/4	8+5/8	24#	906	383	906	0
3RD	7+7/8	5+1/2	17#	9,052	804	9,052	4,652

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments I certify that all conditions in the original permit are the same. There have been no changes to land use, well construction or the lease. This pad is built. No expansion or additional disturbance will occur. Closed loop system will be used.

34. Location ID: 311621

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Ashlie Mihalcin

Title: Permit Representative Date: 10/21/2009 Email: amihalcin@anteroresources.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 12/22/2009

#### API NUMBER

05 045 12417 00

Permit Number: \_\_\_\_\_ Expiration Date: 12/21/2010

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. RESERVE PIT MUST BE LINED. OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL-SITE DURING DRILLING AND COMPLETION OPERATIONS. IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST-MANAGEMENT-PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS. FLOWBACK TO TANKS ONLY. SUBMIT A SECONDARY AND TERTIARY CONTAINMENT PLAN VIA SUNDRY NOTICE FORM 4 FOR THE TANKS. ATTN: LINDA SPRY-O'ROURKE. OBTAIN APPROVAL OF THE PLAN PRIOR TO FLOWBACK. THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 620 FEET DEEP.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400010976	30 DAY NOTICE LETTER	LF@2175795 400010976
400010977	WAIVERS	LF@2175796 400010977

Total Attach: 2 Files