

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

 Refiling ☒  
 Sidetrack ☐

Document Number:

400017626

Plugging Bond Surety

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: LINDA PAVELKA Phone: (303)228-4064 Fax: (303)228-4286

Email: lpavelka@nobleenergyinc.com

7. Well Name: BATTLEMENT MESA Well Number: 34-43D

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 10661

## WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 34 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.388423 Longitude: -107.979840

 Footage at Surface: 656 FNL/FSL 1630 FEL/FWL  
 FSL FEL

11. Field Name: RULISON Field Number: 75400

12. Ground Elevation: 9054 13. County: GARFIELD

## 14. GPS Data:

Date of Measurement: 08/28/2007 PDOP Reading: 2.3 Instrument Operator's Name: ROBERT WOOD

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.
 Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
 1488 FSL 710 FEL 1488 FSL 710 FEL  
 Sec: 34 Twp: 7S Rng: 95W Sec: 34 Twp: 7S Rng: 95W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 4210 ft

18. Distance to nearest property line: 313 ft 19. Distance to nearest well permitted/completed in the same formation: 324 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	139-53	640	NESE

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
SEE LEASE ON FILE

25. Distance to Nearest Mineral Lease Line: 710 ft 26. Total Acres in Lease: 3721

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAP. PIT

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	30	20	LINE PIPE	150	175	150	0
SURF	14+3/4	9+5/8	36	3,300	1,275	3,300	0
1ST	8+3/4	4+1/2	11.6	10,651	1,000	10,651	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments THE PRODUCTION CASING TOP OF CEMENT WILL BE 200' ABOVE TOP OF GAS.  
SURFACE PARASITE STRING TO 3000 FEET.  
ALL CONDITIONS ARE THE SAME AS PRIOR APPROVED PERMIT.  
THE PAD AND ACCESS ROADS WERE NOT BUILT.  
THE LOCATION DOES NOT REQUIRE A VARIANCE FROM ANY OF THE RULES LISTED IN RULE 306.d.(1).(A).(ii).  
THE LOCATION IS NOT IN A WILDLIFE RESTRICTED SURFACE OCCUPANCY AREA.  
DOE WAS NOTIFIED AGAIN ON 12/9/2009 OF TIER 2 PROJECT RULISON SAP STATUS.  
SURFACE OWNER IS CHEVRON.  
THE DRILLING PLANS WERE CHANGED FROM PREVIOUS APPROVED PERMIT.  
THE MUD DISPOSAL WILL BE TO AN EVAPORATION PIT.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: LINDA PAVELKA

Title: REGULATORY MANAGER Date: \_\_\_\_\_ Email: lpavelka@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

**API NUMBER**

05 045 17166 00

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

**Attachment Check List**

Att Doc Num	Name	Doc Description
400020539	30 DAY NOTICE LETTER	_Pad 34O-30day Notice.pdf
400021302	PLAT	BM 34-43D-Plat.pdf
400021306	CORRESPONDENCE	_Pad 34O-DOE Letter.pdf

Total Attach: 3 Files