

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER _____
 SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

 Refiling ☐
 Sidetrack ☐

Document Number:

400008531

Plugging Bond Surety

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: MARI CLARK Phone: (303)228-4413 Fax: (303)228-4286

Email: mclark@nobleenergyinc.com

7. Well Name: BERRY P Well Number: 08-18D

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7404

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 8 Twp: 3N Rng: 67W Meridian: 6

Latitude: 40.246420 Longitude: -104.915870

Footage at Surface: 467 FNL/FSL FNL 2066 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4818 13. County: WELD

14. GPS Data:

Date of Measurement: 07/29/2009 PDOP Reading: 1.7 Instrument Operator's Name: STEVEN A LUND

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.
 Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
 1350 FNL 2450 FWL 1350 FNL 2450 FWL
 Sec: 8 Twp: 3N Rng: 67W Sec: 8 Twp: 3N Rng: 67W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 415 ft

18. Distance to nearest property line: 467 ft 19. Distance to nearest well permitted/completed in the same formation: 881 ft

20.

LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20030012

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
NW/4 SEC. 8, 3N, 67W

25. Distance to Nearest Mineral Lease Line: 125 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	450	188	450	0
1ST	7+7/8	4+1/2	11.6	7,404	430	7,404	0

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. WELL IS TO BE TWINNED WITH EXISTING BERRY 8-3L & PROPOSED BERRY P08-28D, & BERRY P08-29D. AS DRILLED SUNDRY FOR BERRY 8-3L SUBMITTED. CEMENT TOP FOR 1ST STRING WILL BE 200' ABOVE NIOBRARA. UNIT CONFIGURATION = W/2NW/4 & E/2NW/4.

34. Location ID: 329006

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARI CLARK

Title: REG.ANALYST Date: _____ Email: mclark@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Permit Number: _____ Expiration Date: _____

API NUMBER

05

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400020570	WELL LOCATION PLAT	2415-Sharp-5001N_20091208_114009.pdf
400020571	30 DAY NOTICE LETTER	2415-Sharp-5001N_20091208_114022.pdf
400020572	SURFACE AGRMT/SURETY	2415-Sharp-5001N_20091208_114035.pdf
400020573	DEVIATED DRILLING PLAN	2415-Sharp-5001N_20091208_114053.pdf
400020574	PROPOSED SPACING UNIT	2415-Sharp-5001N_20091208_114113.pdf

Total Attach: 5 Files