

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400012203

Plugging Bond Surety

20090078

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling

Sidetrack

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION 4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - SUITE 3000
City: DENVER State: CO Zip: 80203

6. Contact Name: Larry Robbins Phone: (303)860-5822 Fax: (303)860-5838
Email: lrobbins@petd.com

7. Well Name: Puckett Well Number: 33D-24D

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9300

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 24 Twp: 6S Rng: 97W Meridian: 6

Latitude: 39.508473 Longitude: -108.168491

Footage at Surface: 2631 FNL/FSL FSL 2562 FEL/FWL FEL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 8142 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 05/10/2007 PDOP Reading: 2.7 Instrument Operator's Name: Patrick R Green

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
1554 FSL 1961 FEL 1529 FSL 1980 FEL
Sec: 24 Twp: 6S Rng: 97W Sec: 24 Twp: 6S Rng: 97W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 2 mi

18. Distance to nearest property line: 2562 ft 19. Distance to nearest well permitted/completed in the same formation: 330 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork-Cameo	WFCM	510-21		

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached map

25. Distance to Nearest Mineral Lease Line: 2285 ft 26. Total Acres in Lease: 4960

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite
Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	20	53	100	100	100	0
SURF	17+1/2	9+5/8	36	2,500	800	2,500	0
1ST	8+3/4	4+1/2	11.6	9,200	997	9,200	5,375

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Drill pad built, no additional surface disturbance or expansion will occur. No drilling pits due to closed loop system. Mud disposal/lease info updated, drilling plan same as expired permit.

34. Location ID: 335519

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Larry Robbins

Title: Regulatory Agent Date: 11/11/2009 Email: lrobbins@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 1/9/2010

API NUMBER: **05 045 16220 00** Permit Number: _____ Expiration Date: 1/8/2011

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

24 HOUR SPUD NOTICE REQUIRED. E-MAIL: david.andrews@state.co.us GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE CEMENT TOP VERIFICATION BY CBL REQUIRED. OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL SITE DURING DRILLING AND COMPLETION OPERATIONS. IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST MANAGEMENT PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS. THE NEARBY HILLSIDE MUST BE MONITORED FOR ANY DAY LIGHTING DRILLING FLUIDS THROUGHOUT THE DRILLING OF THE SURFACE CASING INTERVAL. COMPLY WITH ALL PROVISIONS OF THE JUNE 12, 2008 NOTICE TO OPERATORS DRILLING WELLS WITHIN 3/4 MILE OF THE RIM OF THE ROAN PLATEAU IN GARFIELD COUNTY - PIT DESIGN, CONSTRUCTION AND MONITORING REQUIREMENTS. SEE ATTACHED NOTICE. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400012248	LEASE MAP	LF@2186234 400012248
400012490	30 DAY NOTICE LETTER	LF@2186235 400012490
400014908	FORM 2 SUBMITTED	LF@2186236 400014908

Total Attach: 3 Files