CASEDHOLE SOLUTIONS

Company SLATE RIVER RESOURCES
Well RUBY 8102-31M
Field BRIDLE
County GARFIELD
State COLORADO

CEMENT BOND LOG

Company	SLATE RIVER RESOURCES		
Well	RUBY 8102-31M		
Field	BRIDLE		
County	GARFIELD	State	COLORADO
Location:	API # : 050770918300 SURFACE 382' FSL & 803' FWL SEC 31 TWP 08S RGE 102W		Other Services
Permanent Datum	GROUND LEVEL	Elevation 4926'	Elevation K.B. 4937' D.F. 4936' G.L. 4926'
Log Measured From	KELLY BUSHING= 11'		
Drilling Measured From	KELLY BUSHING		

Date	4-25-2007	
Run Number	ONE	
Depth Driller	3300'	
Depth Logger	3258'	
Bottom Logged Interval	3248'	
Top Log Interval	300'	
Open Hole Size	7.875	
Type Fluid	2% KCL	
Density / Viscosity		
Max. Recorded Temp.	122 DEG.	
Estimated Cement Top	LOGGED	
Time Well Ready	9:00 AM	
Time Logger on Bottom	10:30 AM	
Equipment Number	113	
Location	VERNAL	
Recorded By	B.LAFOLLETTE	
Witnessed By	MIKE DECKER	

Borehole Record				Tubing Record			
Run Number	Bit	From	To	Size	Weight	From	To

Casing Record	Size	Wgt/Ft	Top	Bottom
Surface String	8.625	24#	SURFACE	300'
Prot. String				
Production String	5.5	17#	SURFACE	T.D.
Liner				

<<< Fold Here >>>

All interpretations are opinions based on inferences from electrical or other measurements and we cannot and do not guarantee the accuracy or correctness of any interpretation, and we shall not, except in the case of gross or willful negligence on our part, be liable or responsible for any loss, costs, damages, or expenses incurred or sustained by anyone resulting from any interpretation made by any of our officers, agents or employees. These interpretations are also subject to our general terms and conditions set out in our current Price Schedule.

Comments

CORRELATED TO HALIBURTON O.H. LOG
DATED 3-27-2007

CASEDHOLE SOLUTIONS

MAIN SECTION "0" PSI

Database File: v-3133.db
Dataset Pathname: pass7
Presentation Format: vcbl
Dataset Creation: Wed Apr 25 10:23:26 2007 by Log Std Casedhole 06040
Charted by: Depth in Feet scaled 1:240

CASEDHOLE SOLUTIONS

REPEAT SECTION "0" PSI

Database File: v-3133.db
Dataset Pathname: pass5
Presentation Format: vcbl
Dataset Creation: Wed Apr 25 10:11:44 2007 by Log Std Casedhole 06040
Charted by: Depth in Feet scaled 1:240



Sensor	Offset (ft)	Schematic	Description	Len (ft)	OD (in)	Wt (lb)
CCL	18.94		CCL-CCLTEK275 (CCLTEK275.01) 2 3/4" TEKCO LOGGING COLLAR LOCATOR	1.83	2.75	20.00
CENT	18.27		CENTTEK1.1 1 3/4" APPLIED CENTRALIZER	2.90	1.75	10.00
CBLTEKCO	15.37					
TEMP	12.73					
WVFCAL	11.29		CBLTEKCO-TEKTP (TEK35_TP275.01) Tekco 2 3/4" Dual Receiver with Temp	9.08	2.75	80.00
WVF3FT	10.54					
WVF5FT	9.54					
WVFTEMP	6.29					
WVFSYNC	6.29					
CENT	6.29		CENTTEK1.1 1 3/4" APPLIED CENTRALIZER	2.90	1.75	10.00
GR	1.29		GR-GRGTEK2.75 (GRGTEK275.01) 2 3/4" TEKCO GIEGER LOGGING GAMMA RAY	3.40	2.75	25.00

Dataset: v-3133.db: field/well/run1/pass7
Total Length: 20.10 ft
Total Weight: 145.00 lb
O.D.: 2.75 in