

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400024993

Plugging Bond Surety

20090077

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☒

Sidetrack ☐

3. Name of Operator: EXXON MOBIL OIL CORPORATION

4. COGCC Operator Number: 28700

5. Address: P O BOX 4358 WGR RM 310

City: HOUSTON State: TX Zip: 77210-4358

6. Contact Name: Mark Cornett Phone: (281)654-1925 Fax: (281)654-1940
Email: mark.cornett@exxonmobil.com

7. Well Name: Piceance Creek Unit Well Number: 297-11C7

8. Unit Name (if appl): Piceance Creek Unit Number: COC047666
A

9. Proposed Total Measured Depth: 13500

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 11 Twp: 2S Rng: 97W Meridian: 6

Latitude: 39.896041 Longitude: -108.254563

Footage at Surface: 992 FNL/FSL 889 FEL/FWL FWL

11. Field Name: Piceance Creek Field Number: 68800

12. Ground Elevation: 6966 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 07/16/2008 PDOP Reading: 1.5 Instrument Operator's Name: D. Petty

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1119 FNL 55 FEL 55 FEL 55 FEL 55
Bottom Hole: FNL/FSL 1119 FNL 55 FEL 55 FEL 55
Sec: 10 Twp: 2S Rng: 97W Sec: 10 Twp: 2S Rng: 97W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 345

18. Distance to nearest property line: 6351 ft 19. Distance to nearest well permitted/completed in the same formation: 597 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Mesaverde	MVRD			
Ohio Creek	OHCRK			
Wasatch	WSTC			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COD035705

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Submitted with initial APD. No changes.

25. Distance to Nearest Mineral Lease Line: 1154 ft 26. Total Acres in Lease: 2247

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Burial

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	16	84	117	143	117	0
SURF	14+3/4	10+3/4	45.5	3,868	1,151	3,868	0
1ST	9+7/8	7	26	8,700	640	8,700	3,369
2ND	6+1/8	4+1/2	15.1	12,887	271	12,887	6,314

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Current APD expires 02/24/2010. No changes to surrounding land use. Location has been built, conductors set for all wells (9) and rig is currently on location drilling other wells on pad. Updated casing setting depth/cement info., which was previously approved (11/17/09) via sundry notice, is reflected on this filing.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Mark Cornett

Title: Regulatory Specialist Date: 12/29/2009 Email: mark.cornett@exxonmobil.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 2/4/2010

API NUMBER

05 103 11469 00

Permit Number: _____ Expiration Date: 2/3/2011

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) 24-HOUR SPUD NOTICE REQUIRED. E-MAIL Shaun.Kellerby@state.co.us (2) RESERVE PIT MUST BE LINED. (3) CEMENT-TOP VERIFICATION BY CBL REQUIRED. (4) OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL-SITE DURING DRILLING AND COMPLETION OPERATIONS. IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST-MANAGEMENT-PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS. (5) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. (6) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT. (7) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400025111	FORM 2 SUBMITTED	LF@2209745 400025111

Total Attach: 1 Files