

WALKER USX ABØ1-15P  
SW¼SE¼ 1-7N-64W

## Map Unit Description

Weld County, Colorado, Northern Part

### 44 Olney fine sandy loam, 0 to 6 percent slopes

#### Setting

Elevation: 3500 to 5800 feet  
Mean annual precipitation: 11 to 15 inches  
Mean annual air temperature: 46 to 54 degrees F  
Frost-free period: 125 to 175 days

#### Composition

Olney and similar soils: 85 percent  
Minor components: 15 percent

#### Description of Olney

##### Setting

Landform: Plains  
Down-slope shape: Linear  
Across-slope shape: Linear  
Parent material: Calcareous loamy alluvium

##### Properties and Qualities

Slope: 0 to 6 percent  
Drainage class: Well drained  
Capacity of the most limiting layer to transmit water (Ksat): Moderately high or high (0.57 to 2.00 in/hr)  
Frequency of flooding: None  
Frequency of ponding: None  
Calcium carbonate maximum: 15 percent  
Gypsum maximum: 0 percent  
Available water capacity: Moderate (about 8.1 inches)

##### Interpretive Groups

Land capability (non irrigated): 4c  
Ecological site: Loamy Plains (R067BY002CO)

##### Typical Profile

0 to 6 inches: fine sandy loam  
6 to 18 inches: sandy clay loam  
18 to 60 inches: sandy loam  
60 to 64 inches: sandy loam

#### Minor Components

##### Stoneham

Percent of map unit: 9 percent

##### Ascalon

Percent of map unit: 6 percent