

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400031395

Plugging Bond Surety

20030009

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐Refiling ☐Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: Jennifer Barnett Phone: (303)228-4342 Fax: (303)228-4286

Email: jbarnett@nobleenergyinc.com

7. Well Name: Battlement Mesa Well Number: 35-11A

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 10906

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 35 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.397514 Longitude: -107.973517

Footage at Surface: 1224 FNL/FSL FNL 155 FEL/FWL FWL

11. Field Name: Parachute Field Number: 67350

12. Ground Elevation: 8846.8 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 09/09/2009 PDOP Reading: 2.3 Instrument Operator's Name: Robert Wood

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone:	FNL/FSL	FEL/FWL	Bottom Hole:	FNL/FSL	FEL/FWL
126	FNL	695	FWL	112	FNL
				618	FWL
Sec: 35	Twp: 7S	Rng: 95W	Sec: 35	Twp: 7S	Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 7475 ft

18. Distance to nearest property line: 155 ft 19. Distance to nearest well permitted/completed in the same formation: 315 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	139-53	40	NWNW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20030012

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Please see attached mineral lease map.

25. Distance to Nearest Mineral Lease Line: 618 ft 26. Total Acres in Lease: 2686

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Evap Pond

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	30	20		150	175	150	0
SURF	14+3/4	9+5/8	36	3,300	1,275	3,300	0
1ST	8+3/4	4+1/2	11.6	10,896	1,000	10,906	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments This well is in the Rullison Tier II. DOE notice was sent on 2/12/2010. The cement top for the first string will be 200' above TOG. A parasite string will be set with the surface casing to 3000 feet. Operator is the surface owner. This well is part of the Battlement Mesa 35D2 pad.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jennifer Barnett

Title: Regulatory Analyst Date: _____ Email: jbarnett@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Permit Number: _____ Expiration Date: _____

API NUMBER

05

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400039559	WELL LOCATION PLAT	Battlement Mesa 35-11A well location plat.pdf
400039560	TOPO MAP	BM 35D2 pad topographic map.pdf
400039561	MINERAL LEASE MAP	BM 35D2 pad mineral lease map.pdf
400039562	DEVIATED DRILLING PLAN	Battlement Mesa 35-11A deviated drilling plan.pdf

Total Attach: 4 Files