

Beddo P25-28D

T3N, R67W 6th P.M.  
Section 25: SWNE

## Map Unit Description

Weld County, Colorado, Southern Part

### 3 Aquolls and Aquepts, gravelly substratum

#### Setting

Elevation: 4000 to 7200 feet  
Mean annual precipitation: 12 to 18 inches  
Mean annual air temperature: 45 to 55 degrees F  
Frost-free period: 80 to 155 days

#### Composition

Aquolls and similar soils: 55 percent  
Aquepts, gravelly substratum, and similar soils: 30 percent  
Minor components: 15 percent

#### Description of Aquolls

##### Setting

Landform: Swales, streams, flood plains  
Down-slope shape: Linear  
Across-slope shape: Linear  
Parent material: Recent alluvium

##### Properties and Qualities

Slope: 0 to 3 percent  
Drainage class: Poorly drained  
Capacity of the most limiting layer to transmit water (Ksat): Moderately high or high (0.20 to 2.00 in/hr)  
Depth to water table: About 6 to 48 inches  
Frequency of flooding: Frequent  
Frequency of ponding: None  
Calcium carbonate maximum: 0 percent  
Gypsum maximum: 0 percent  
Available water capacity: Moderate (about 8.0 inches)

##### Interpretive Groups

Land capability (non irrigated): 6w  
Ecological site: Salt Meadow (R067BY035CO)

##### Typical Profile

0 to 48 inches: loam  
48 to 60 inches: gravelly sand

#### Description of Aquepts, gravelly substratum

##### Setting

Landform: Stream terraces  
Down-slope shape: Linear  
Across-slope shape: Linear  
Parent material: Recent alluvium

##### Properties and Qualities

Slope: 0 to 3 percent  
Drainage class: Poorly drained  
Capacity of the most limiting layer to transmit water (Ksat): Moderately high or very high (0.57 to 19.98 in/hr)  
Depth to water table: About 6 to 24 inches  
Frequency of flooding: Frequent  
Frequency of ponding: None  
Calcium carbonate maximum: 10 percent  
Gypsum maximum: 0 percent  
Available water capacity: Moderate (about 6.6 inches)

##### Interpretive Groups

Land capability classification (irrigated): 6w  
Land capability (non irrigated): 6w  
Ecological site: Salt Meadow (R067BY035CO)

##### Typical Profile

0 to 48 inches: variable  
48 to 60 inches: very gravelly sand

Beddo P25-28D

T3N, R67W 6th P.M.  
Section 25: SWNE

### Map Unit Description

Weld County, Colorado, Southern Part

#### Minor Components

##### Bankard

Percent of map unit: 10 percent

##### Ustic torrifluvents

Percent of map unit: 5 percent