

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

2094529

Plugging Bond Surety

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☐ COALBED ☐ OTHER OIL AND GAS
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☒

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: NICK G. CURRAN Phone: (720)876-5288 Fax: (720)876-6288
Email: NICK.CURRAN@ENCANA.COM

7. Well Name: VESSELS MINERALS Well Number: 4-0-30

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8566

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 30 Twp: 1N Rng: 68W Meridian: 6

Latitude: 40.026300 Longitude: -105.049490

Footage at Surface: 1088 FNL/FSL FNL 1641 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 5075 13. County: WELD

14. GPS Data:

Date of Measurement: 12/10/2009 PDOP Reading: 1.4 Instrument Operator's Name: TOM WINANS

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 300 FNL 2483 FWL 300 FNL 2483 FWL
Bottom Hole: FNL/FSL 300 FNL 2483 FWL
Sec: 30 Twp: 1N Rng: 68W Sec: 30 Twp: 1N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1125 ft

18. Distance to nearest property line: 372 ft 19. Distance to nearest well permitted/completed in the same formation: 1196 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407	160	GWA
J SAND	JSND	232-23	160	GWA
NIOBRARA	NBRR	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T1N-R68W: SEC. 19-W2SW; SEC. 30-W2; SEC. 31-W2W2

25. Distance to Nearest Mineral Lease Line: _____ 49 ft 26. Total Acres in Lease: _____ 555

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	840	280	840	0
1ST	7+7/8	4+1/2	11.6	8,566	320	8,566	7,360

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. PROPSD SPACING UNIT IS SESW, SWSE, SEC 19; NENW, NWNE, SEC 30 Well included on Form 2A (Document Number 1904646), expiration date: 09/28/2012.

34. Location ID: _____ 335763

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: NICK G. CURRAN

Title: PERMITTING AGENT Date: 1/13/2010 Email: NICK.CURRAN@ENCANA.CO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 2/25/2010

API NUMBER

05 123 30076 00

Permit Number: _____ Expiration Date: 2/24/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Note surface casing setting depth change from 650' to 840'. Increase cement coverage accordingly and cement to surface. 2) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 3) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log. 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1760454	SURFACE AGRMT/SURETY	LF@2423170 1760454
2094529	APD ORIGINAL	LF@2215713 2094529
2094530	WELL LOCATION PLAT	LF@2215714 2094530
2094531	TOPO MAP	LF@2215715 2094531
2094532	MINERAL LEASE MAP	LF@2215793 2094532
2094533	SURFACE AGRMT/SURETY	LF@2215716 2094533
2094534	30 DAY NOTICE LETTER	LF@2215717 2094534
2094535	DEVIATED DRILLING PLAN	LF@2215718 2094535
2094536	PROPOSED SPACING UNIT	LF@2215719 2094536
400030996	FORM 2 SUBMITTED	LF@2243636 400030996

Total Attach: 10 Files