

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:
2094522
Plugging Bond Surety
20050043

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

3. Name of Operator: ENCANA OIL & GAS (USA) INC 4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700
City: DENVER State: CO Zip: 80202-5632

6. Contact Name: NICK G. CURRAN Phone: (720)876-5288 Fax: (720)876-6288
Email: NICK.CURRAN@ENCANA.COM

7. Well Name: VESSELS MINERALS Well Number: 22-30

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8586

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 30 Twp: 1N Rng: 68W Meridian: 6
Latitude: 40.026250 Longitude: -105.049490

Footage at Surface: 1108 FNL/FSL FNL 1641 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 5075 13. County: WELD

14. GPS Data:

Date of Measurement: 12/10/2009 PDOP Reading: 1.0 Instrument Operator's Name: TOM WINANS

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2130 FNL 2105 FWL 2130 FNL 2105 FWL
Sec: 30 Twp: 1N Rng: 68W Sec: 30 Twp: 1N Rng: 68W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 1145 ft

18. Distance to nearest property line: 372 ft 19. Distance to nearest well permitted/completed in the same formation: 1008 ft

20. **LEASE, SPACING AND POOLING INFORMATION**

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407	320	W/2
J SAND	JSND	232-23	320	W/2
NIOBRARA	NBRR	407	320	W/2

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T1N-R68W SEC. 19-W2SW; SEC. 30-W2; SEC. 31 W2W2

25. Distance to Nearest Mineral Lease Line: 442 ft 26. Total Acres in Lease: 555

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite
Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	840	280	840	0
1ST	7+7/8	4+1/2	11.6	8,586	320	8,586	7,366

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: 335763

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: NICK G. CURRAN

Title: PERMITTING Date: 1/13/2010 Email: NICK.CURRAN@ENCANA.CO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 2/25/2010

Permit Number: _____ Expiration Date: 2/24/2012

API NUMBER
05 123 30009 00

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Note surface casing setting depth change from 650' to 840'. Increase cement coverage accordingly and cement to surface. 2) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 3) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log. 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1760456	SURFACE AGRMT/SURETY	LF@2423200 1760456
2094522	APD ORIGINAL	LF@2215720 2094522
2094523	WELL LOCATION PLAT	LF@2215721 2094523
2094524	TOPO MAP	LF@2215722 2094524
2094525	MINERAL LEASE MAP	LF@2215794 2094525
2094526	SURFACE AGRMT/SURETY	LF@2215723 2094526
2094527	30 DAY NOTICE LETTER	LF@2215724 2094527
2094528	DEVIATED DRILLING PLAN	LF@2215725 2094528
400030930	FORM 2 SUBMITTED	LF@2221498 400030930

Total Attach: 9 Files