

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



| | | | |
|----|----|----|----|
| DE | ET | OE | ES |
|----|----|----|----|

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling

Sidetrack

Document Number:

2585365

Plugging Bond Surety

20030107

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: LISA Dee Phone: (303)260-4538 Fax: (303)629-8268

Email: LISA.DEE@WILLIAMS.COM

7. Well Name: CHEVRON Well Number: TR 424-28-597

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9170

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 28 Twp: 5S Rng: 97W Meridian: 6

Latitude: 39.580015 Longitude: -108.285394

Footage at Surface: 948 FNL/FSL FSL 1953 FEL/FWL FWL

11. Field Name: TRAIL RIDGE Field Number: 83825

12. Ground Elevation: 8374 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 01/05/2009 PDOP Reading: 1.0 Instrument Operator's Name: PAT MCLINSKEY

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 616 FSL 1923 FWL FWL Bottom Hole: FNL/FSL 616 FSL 1923 FWL FWL

Sec: 28 Twp: 5S Rng: 97W Sec: 28 Twp: 5S Rng: 97W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 17424 ft

18. Distance to nearest property line: 6494 ft 19. Distance to nearest well permitted/completed in the same formation: 342 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| ILES | ILES | 510-44 | | |
| WILLIAMS FORK | WMFK | 510-17 | | |

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED.

25. Distance to Nearest Mineral Lease Line: 2073 ft 26. Total Acres in Lease: 17315

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: EVAPORATION AND BACK

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Weight Per Foot | Setting Depth | Sacks Cement | Cement Bottom | Cement Top |
|-------------|--------------|----------------|-----------------|---------------|--------------|---------------|------------|
| CONDUCTOR | 24 | 18 | 48 | 60 | 100 | 60 | 0 |
| SURF | 14+3/4 | 9+5/8 | 32.3 | 2,554 | | 2,554 | 0 |
| 1ST | 7+7/8 | 4+1/2 | 11.6 | 9,170 | | 9,170 | |

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments CEMENT WILL BE CIRCULATED TO THE SURFACE IN THE CONDUCTOR & SURFACE STRINGS. CEMENT WILL BE CIRCULATED TO 200' ABOVE THE UPPERMOST MESAVERDE SAND IN THE PRODUCTION STRING. LOCATION CONSTRUCTED. NO EXPANSION NEEDED - NO ADDITIONAL SURFACE DISTURBANCE. NEW PRODUCTION PIT WILL BE DUG - SEE 2A FOR DETAILS. BHL AND TD SHIFT. REVISED WELL PLAT AND DIRECTIONAL INCLUDED.

34. Location ID: 335925

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: LISA DEE

Title: REGULATORY Date: 12/22/2009 Email: LISA.DEE@WILLIAMS.COM

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 2/26/2010

Permit Number: _____ Expiration Date: 2/25/2012

API NUMBER

05 045 17817 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)24 HOUR SPUD NOTICE REQUIRED. E-MAIL: Shaun.Kellerby@state.co.us 2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE 3)CEMENT TOP VERIFICATION BY CBL REQUIRED. 4)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

| Att Doc Num | Name | Doc Description |
|-------------|------------------------|----------------------|
| 2585365 | APD ORIGINAL | LF@2204595 2585365 |
| 2585366 | WELL LOCATION PLAT | LF@2204596 2585366 |
| 2585367 | DEVIATED DRILLING PLAN | LF@2204597 2585367 |
| 400025129 | FORM 2 SUBMITTED | LF@2208940 400025129 |

Total Attach: 4 Files