

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400030955

Plugging Bond Surety

20090078

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refilling ☐

Sidetrack ☐

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - SUITE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Sarah Garrett Phone: (303)860-5803 Fax: (303)860-5838

Email: sgarrett@petd.com

7. Well Name: Wells Ranch Well Number: 360

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 6900

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 36 Twp: 6N Rng: 63W Meridian: 6

Latitude: 40.442690 Longitude: -104.385510

Footage at Surface: 2572 FNL/FSL FSL 2564 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4730 13. County: WELD

14. GPS Data:

Date of Measurement: 01/05/2010 PDOP Reading: 6.0 Instrument Operator's Name: Thomas G Carlson PLS 24657

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 4 mi

18. Distance to nearest property line: 2564 ft 19. Distance to nearest well permitted/completed in the same formation: 830 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J Sand	JSND		160	GWA
Niobrara Codell	NB-CD	407-87	160	GWA
Sussex Shannon	SX-SN	N/A	160	GWA

21. Mineral Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Section 36, Township 6 North, Range 63 West

25. Distance to Nearest Mineral Lease Line: 2564 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	500	300	500	0
1ST	7+7/8	4+1/2	10.5	6,900	180	6,900	5,700

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. Well will be tied into a common tank battery at the existing Wells Ranch 36B location. A separate 2A will be filed if necessary. Proposed spacing unit NESW, NWSE, SENW, SWNE Sec 36

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Sarah Garrett

Title: Landman Date: 1/21/2010 Email: sgarrett@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 2/26/2010

API NUMBER

05 123 31202 00

Permit Number: _____ Expiration Date: 2/25/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COGCC ENG COA – SME 1) Provide 24 hr notice of spud to Provide 24 hour notice of MIRU to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us. 2. Set surface casing, per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If completed comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log. Restore surface location.

Location is outside the drilling window and is more than 50 feet from an existing well; excptions granted

Location is outside the drilling window and is more than 50 feet from an existing well; excptions granted

Attachment Check List

Att Doc Num	Name	Doc Description
1725523	SURFACE CASING CHECK	LF@2363942 1725523
400030960	30 DAY NOTICE LETTER	LF@2221133 400030960
400030961	PLAT	LF@2221135 400030961
400030962	TOPO MAP	LF@2221137 400030962
400030963	EXCEPTION LOC WAIVERS	LF@2221140 400030963
400030965	EXCEPTION LOC REQUEST	LF@2395133 400030965
400030966	PROPOSED SPACING UNIT	LF@2395134 400030966
400030968	PROPOSED SPACING UNIT	LF@2395135 400030968
400030990	FORM 2 SUBMITTED	LF@2395136 400030990

Total Attach: 9 Files