



02054279



# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 (303) 894-2100 Fax: (303) 894-2109

FOR OGCC USE ONLY  
**RECEIVED**

MAR 09 2010

**COGCC****LOSS OF WELL CONTROL REPORT**

As required by Rule 327.

**Report taken by:**

DAVE ANDREWS

1. OGCC Operator Number: 100185

2. Name of Operator: EnCana Oil &amp; Gas (USA) Inc.

3. Address: 370 17th Street, Suite 1700

City: Denver

State: CO

Zip: 80202

4. Contact Name &amp; Phone

Steven Henning

Ph: 720-876-5329

Fax: 720-876-6329

**WELL LOCATION INFORMATION**

5. API Number: 05-045-18919-00

6. County: GARFIELD

7. Well Name: N PARACHUTE

8. Well Number: WF16A-21 K22 596

9. Unit Name (if appl.):

10. Unit No:

11. QtrQtr: NESW

Sec: 22

Twp: 5S

Rng: 96W

Meridian: 6

12. Footage From Exterior Section Lines: 2125' FSL 1573' FWL

13. Field Name: GRAND VALLEY

14. Field Number: 31290

**CASING INFORMATION**

15. Surface Casing Size: 9-5/8" / Weight per Foot: 36# Grade: J-55 True Vertical Setting Depth: 1683'

16. Intermed. Casing Size: / Weight per Foot: Grade: True Vertical Setting Depth:

**KICK INFORMATION**

17. True Vertical Depth at Kick: 8687'

18. Formation at Kick: Williams Fork

19. Formation Code: WMFK

20. Shut-in Drill Pipe Pressure (SIDPP): 0 (float) / 150 (bump float) psi.

21. Shut-in Casing Pressure (SICP): 150 psi.

22. Mud Weight at Time of Kick: 10.3 ppg.

23. Pit Gain: 28 bbls.

24. Time and Date Shut In: 10:00 PM 03/07/2010

25. Mud Weight Required to Control Well: 10.6 ppg.

26. Type of Kick: ☒ Gas ☐ Oil ☐ Water

27. Comments (describe actions to control in detail): Eventually weighted up to 11.0 ppg to control background gas/flare before resumption of drilling.