

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400034544

Plugging Bond Surety

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☒

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: MIRACLE PFISTER Phone: (720)876-3761 Fax: (720)876-6060
Email: miracle.pfister@encana.com

7. Well Name: GMU Well Number: 27-9C (L26NW)

8. Unit Name (if appl): GRASS MESA UNIT Unit Number: COC56608A

9. Proposed Total Measured Depth: 8949

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 26 Twp: 6S Rng: 93W Meridian: 6

Latitude: 39.494250 Longitude: -107.751420

Footage at Surface: 1488 FNL/FSL FSL 214 FEL/FWL FWL

11. Field Name: MAMM CREEK Field Number: 52500

12. Ground Elevation: 6254.5 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 04/21/2008 PDOP Reading: 0.0 Instrument Operator's Name: T. TAGGART

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1545 FSL 820 FEL FEL Bottom Hole: FNL/FSL 1545 FSL 820 FEL FEL
Sec: 27 Twp: 6S Rng: 93W Sec: 27 Twp: 6S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1760 ft

18. Distance to nearest property line: 168 ft 19. Distance to nearest well permitted/completed in the same formation: 637 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES			
WILLIAMS FORK	WMFK			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC54737

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T6S-R93W 6TH PM SEC 26: NW, N2SW, SESW SEC 27: E/2NW, NE/SE, SW/SE SEC 28: SE/SW SEC 33: NW, W/2SW SEC 34: SE/NE/E2SE, SEC 35: W2NW, S2/SW

25. Distance to Nearest Mineral Lease Line: 221 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	16	LINEPIPE	40	5	40	0
SURF	12+1/4	9+5/8	36	1,262	339	1,262	0
1ST	8+3/4	4+1/2	11.6	8,949	1,063	8,949	0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments A form 2A is not required for this refile based on the following: 1- The pad has been built. 2 - No frac pit is planned for this location. A cuttings pit will be used. 3 - The refile will not require any expansion/additional surface disturbance of the pad. 4 - The locatin does not require a variance from any of the riles listed in rule 306.d (1).(A). (ii). 5 - The location is not in a wildlife restricted surface occupancy area. No changes are being made to the drilling plan from what has already been approved on the original APD and sundry previously submitted. The production casing top of cement will be 500>TOG>

34. Location ID: 383338

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MIRACLE PFISTER

Title: REGULATORY ANALYST Date: 2/1/2010 Email: miracle.pfister@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David G. Neslin Director of COGCC Date: 3/15/2010

Permit Number: _____ Expiration Date: 3/14/2011

API NUMBER

05 045 18359 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) 24-HOUR SPUD NOTICE REQUIRED.E-MAIL Shaun.Kellerby@state.co.us (2)GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS.NOTE:ALL NOTICES SHALL BE GIVEN VIA E-MAIL.SEE ATTACHED NOTICE. (3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL.NOTE:ALL NOTICES SHALL BE GIVEN VIA E-MAIL.SEE ATTACHED NOTICE. (4)SURFACE CASING MUST BE RUN TO A MINIMUM DEPTH OF 1245'. (5)THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS.AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. (6)NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT.THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT.THE ENTIRE BASE OF THE PIT MUST BE IN CUT. (7)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES.THE DEEPEST WATER WELL WITHIN 1-MILE IS 520 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400039345	FORM 2 SUBMITTED	LF@2420854 400039345

Total Attach: 1 Files