

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400035836

Plugging Bond Surety

20040060

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BARRETT CORPORATION* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: Matt Barber Phone: (303)312-8168 Fax: (303)291-0420
Email: mbarber@billbarrettcorp.com

7. Well Name: Kaufman Well Number: 42D-25-692

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7435

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 30 Twp: 6S Rng: 91W Meridian: 6

Latitude: 39.503013 Longitude: -107.604506

Footage at Surface: 968 FNL/FSL FNL 448 FEL/FWL FWL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 5786.5 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 12/21/2009 PDOP Reading: 6.0 Instrument Operator's Name: James A Kalmon

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1501 FNL 660 FEL 660 FEL 1501 FNL 660 FEL 660
Sec: 25 Twp: 6S Rng: 92W Sec: 25 Twp: 6S Rng: 92W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 251 ft

18. Distance to nearest property line: 223 ft 19. Distance to nearest well permitted/completed in the same formation: 334 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	191-10	640	All
Williams Fork	WMFK	191-8	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached Lease Boundary Map

25. Distance to Nearest Mineral Lease Line: 683 ft 26. Total Acres in Lease: 2226

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Evaporation & Backfilling

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	16	42	40		40	0
SURF	12+1/4	9+5/8	36	760	240	760	0
1ST	8+3/4	4+1/2	11.6	7,435	590	7,435	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Casing comments: production string second hole size = 7 7/8, production cement top = 500' above top of gas

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Matt Barber

Title: Permit Analyst Date: 3/15/2010 Email: mbarber@billbarrettcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400035838	DEVIATED DRILLING PLAN	42D Deviated Drilling Plan.pdf
400035839	DRILLING PLAN	42D Drilling Plan.pdf
400035840	LOCATION DRAWING	42D Location Drawing.pdf
400035841	WELL LOCATION PLAT	42D Well Location Plat.pdf
400035843	ACCESS ROAD MAP	Pad 4 Access Road Map.pdf
400035875	LEASE MAP	Kaufman 4 Lease Boundary Map.pdf
400046961	SURFACE AGRMT/SURETY	Memo Surface Damage & Rel Agmt 758784.pdf
400047959	FORM 2 SUBMITTED	400047959.pdf

Total Attach: 8 Files