

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400035285

Plugging Bond Surety

20060137

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: OXY USA WTP LP

4. COGCC Operator Number: 66571

5. Address: P O BOX 27757

City: HOUSTON State: TX Zip: 77227

6. Contact Name: Joan Proulx Phone: (970)263-3641 Fax: (970)263-3694  
Email: joan\_proulx@oxy.com

7. Well Name: Shell Well Number: 697-34-24

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7157

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 3 Twp: 7S Rng: 97W Meridian: 6

Latitude: 39.478406 Longitude: -108.201956

Footage at Surface: 1224 FNL/FSL FNL 1479 FEL/FWL FEL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 6329 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 07/05/2007 PDOP Reading: 2.7 Instrument Operator's Name: Brian Baker

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 367 FSL 223 FEL 504 FEL/FWL 195 FEL 504  
Sec: 34 Twp: 6S Rng: 97W Sec: 34 Twp: 6S Rng: 97W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2 mi

18. Distance to nearest property line: 1165 ft 19. Distance to nearest well permitted/completed in the same formation: 341 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
William Fork	WMFK	510-26		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached Mineral Lease Description

25. Distance to Nearest Mineral Lease Line: 195 ft 26. Total Acres in Lease: 4764

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Reserve pit

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20+0/0	16+0/0	65#	80	0	80	0
SURF	12+1/4	9+5/8	36#	1,000	599	1,000	0
1ST	8+3/4	4+1/2	11.6#	7,157	1,571	7,157	3,320

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Oxy is both the surface and mineral owner. Rule 305 and 306 are waived . The well pad has been constructed, there are no producing wells on this location; there is currently no drilling rig on this pad. Drilling operations are projected to commence sometime in 2010. Since the last permit was filed, there have not been any changes in the lease or mineral situation and surface location. The well pad will not need to be altered. A semi-closed loop system will be used. Per GarCo Vacation Ordinance dated 10-5-1987, CR 213 is now OXY's private property north of Sec 8, 7S, 97W, 6 PM. Oxy will comply with new "Notice to Operators" regarding reserve pits (June 12, 2008). This location does not require a variance to any of the rules in 306.d.(1).(A).(ii) and this location is not located in an RSO area. 2-19-10 JLV 1. The pad has been built  
2. The pit has been constructed.  
3. The refiled wells will not require any expansion/additional surface disturbance of the pad.  
4. The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A). (ii).  
5. The location is not in a wildlife restricted surface occupancy area.  
Per correspondence with Joan Proux 03/23/2010 RE

34. Location ID: 335482

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Joan Proulx

Title: Regulatory Analyst Date: 2/3/2010 Email: joan\_proulx@oxy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

*David S. Neslin*

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: 3/26/2010

**API NUMBER**

05 045 18386 00

Permit Number: \_\_\_\_\_ Expiration Date: 3/25/2011

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)24 HOUR SPUD NOTICE REQUIRED. E-MAIL: Shaun.Kellerby@state.co.us 2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE 3)RESERVE PIT MUST BE LINED. 4)CEMENT TOP VERIFICATION BY CBL REQUIRED. 5)OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL SITE DURING DRILLING AND COMPLETION OPERATIONS.IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST MANAGEMENT PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS. 6)THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. 7)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400039402	FORM 2 SUBMITTED	LF@2421866 400039402

Total Attach: 1 Files