

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



|    |    |    |    |
|----|----|----|----|
| DE | ET | OE | ES |
|----|----|----|----|

Document Number:

400033857

Plugging Bond Surety

20030107

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☒

Sidetrack ☐

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: Howard Harris Phone: (303)606-4086 Fax: (303)629-8272

Email: howard.harris@williams.com

7. Well Name: Mahaffey Well Number: PA 44-25

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8293

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 25 Twp: 6S Rng: 95W Meridian: 6

Latitude: 39.490478 Longitude: -107.947988

Footage at Surface: 684 FNL/FSL FSL 2351 FEL/FWL FWL

11. Field Name: Parachute Field Number: 67350

12. Ground Elevation: 5176 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 05/05/2008 PDOP Reading: 5.9 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1121 FSL 623 FEL FEL Bottom Hole: FNL/FSL 1121 FSL 623 FEL FEL  
Sec: 25 Twp: 6S Rng: 95W Sec: 25 Twp: 6S Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 300 ft

18. Distance to nearest property line: 244 ft 19. Distance to nearest well permitted/completed in the same formation: 308 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| Williams Fork          | WMFK           | 440-51                  | 160                           | SE/4                                 |

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See Attached

25. Distance to Nearest Mineral Lease Line: 623 ft 26. Total Acres in Lease: 810

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-Use and Evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Weight Per Foot | Setting Depth | Sacks Cement | Cement Bottom | Cement Top |
|-------------|--------------|----------------|-----------------|---------------|--------------|---------------|------------|
| CONDUCTOR   | 24           | 18             | 48              | 45            | 25           | 45            | 0          |
| SURF        | 13+1/2       | 9+5/8          | 32.3            | 1,261         | 440          | 1,261         | 0          |
| 1ST         | 7+7/8        | 4+1/2          | 11.6            | 8,293         | 622          | 8,293         | 4,467      |

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Pad and pits have been constructed, no additional expansion is necessary. There have been no changes to lease conditions, drilling plan, etc since original form 2 was issued, Pad is not in an RSO or 317B area. The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii). per Howard Harris 02/18/10. ksc 160 acre unit with 178 total acres, permitting 12 wells at this time for a total of 16 wells when fully developed. Closed mud system

34. Location ID: 383332

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Howard Harris

Title: Sr. Regulatory Specialist Date: 2/3/2010 Email: howard.harris@williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 3/26/2010

Permit Number: \_\_\_\_\_ Expiration Date: 3/25/2011

**API NUMBER**

05 045 18294 00

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)24 HOUR SPUD NOTICE REQUIRED. E-MAIL: Shaun.Kellerby@state.co.us 2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE 3)CEMENT TOP VERIFICATION BY CBL REQUIRED. 4)OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL SITE DURING DRILLING AND COMPLETION OPERATIONS.IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST MANAGEMENT PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS. 5)FLOWBACK TO TANKS ONLY.SUBMIT A SECONDARY AND TERTIARY CONTAINMENT PLAN VIA SUNDRY NOTICE FORM 4 FOR THE TANKS. ATTN: CHRIS CANFIELD. OBTAIN APPROVAL OF THE PLAN PRIOR TO FLOWBACK. 6)THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. 7)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 205 FEET DEEP.

**Attachment Check List**

| Att Doc Num | Name             | Doc Description      |
|-------------|------------------|----------------------|
| 400039313   | FORM 2 SUBMITTED | LF@2420541 400039313 |

Total Attach: 1 Files