

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
400031771
Plugging Bond Surety
20060137

3. Name of Operator: OXY USA WTP LP 4. COGCC Operator Number: 66571

5. Address: P O BOX 27757
City: HOUSTON State: TX Zip: 77227

6. Contact Name: Joan Proulx Phone: (970)263-3641 Fax: (970)263-3694
Email: joan_proulx@oxy.com

7. Well Name: Cascade Creek Well Number: 697-08-54B

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9089

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 9 Twp: 6S Rng: 97W Meridian: 6
Latitude: 39.530619 Longitude: -108.233208

Footage at Surface: 151 FNL/FSL FSL 264 FEL/FWL FWL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 8396 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 12/14/2009 PDOP Reading: 1.5 Instrument Operator's Name: John Richardson

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
680 FSL 1759 FEL 710 FSL 1873 FEL
Sec: 8 Twp: 6S Rng: 97W Sec: 8 Twp: 6S Rng: 97W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 3 mi

18. Distance to nearest property line: 5005 ft 19. Distance to nearest well permitted/completed in the same formation: 326 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-15		

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached mineral lease description

25. Distance to Nearest Mineral Lease Line: 3473 ft 26. Total Acres in Lease: 9480

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: Reserve pit

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20+0/0	16+0/0	65#	100	0	100	0
SURF	14+3/4	9+5/8	36#	2,690	1,420	2,690	0
1ST	8+3/4	4+1/2	11.6#	9,089	2,146	9,089	5,611

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Oxy is both the surface and mineral owner. Rule 305 and 306 are waived . The well pad has been constructed, there are no producing wells on this location; there is currently no drilling rig on this pad. Drilling operations are projected to commence sometime in 2010. The well pad will not need to be altered. A semi-closed loop system will be used. Per GarCo Vacation Ordinance dated 10-5-1987, CR 213 is now OXY's private property north of Sec 8, 7S, 97W, 6 PM. Oxy will comply with new "Notice to Operators" regarding reserve pits (June 12, 2008). (revised comments jps 3/25)

34. Location ID: 336005

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Joan Proulx

Title: Regulatory Analyst Date: 1/25/2010 Email: joan_proulx@oxy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 3/30/2010

Permit Number: _____ Expiration Date: 3/29/2012

API NUMBER

05 045 19287 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)24 HOUR SPUD NOTICE REQUIRED. E-MAIL: Shaun.Kellerby@state.co.us 2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE 3)CEMENT TOP VERIFICATION BY CBL REQUIRED. 4)COMPLY WITH ALL PROVISIONS OF THE JUNE 12, 2008 NOTICE TO OPERATORS DRILLING WELLS WITHIN 3/4 MILE OF THE RIM OF THE ROAN PLATEAU IN GARFIELD COUNTY - PIT DESIGN, CONSTRUCTION AND MONITORING REQUIREMENTS. SEE ATTACHED NOTICE. 5)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400031810	PLAT	LF@2338459 400031810
400031811	DEVIATED DRILLING PLAN	LF@2338460 400031811
400031812	LEGAL/LEASE DESCRIPTION	LF@2338461 400031812
400031814	TOPO MAP	LF@2338462 400031814
400031823	FORM 2 SUBMITTED	LF@2338463 400031823

Total Attach: 5 Files