

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐  
Sidetrack ☐

Document Number:

400014937

Plugging Bond Surety

20040105

3. Name of Operator: BERRY PETROLEUM COMPANY

4. COGCC Operator Number: 10091

5. Address: 1999 BROADWAY STE 3700

City: DENVER State: CO Zip: 80202

6. Contact Name: JANNI KEIDEL Phone: (303)999-4225 Fax: (303)999-4325  
Email: jek@bry.com

7. Well Name: OXY Well Number: 22-11D

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 9129

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 22 Twp: 6S Rng: 97W Meridian: 6

Latitude: 39.502550 Longitude: -108.201972

Footage at Surface: 476 FNL/FSL FSL 1478 FEL/FWL FEL

11. Field Name: GRAND VALLEY Field Number: 31290

12. Ground Elevation: 8491 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/05/2009 PDOP Reading: 1.9 Instrument Operator's Name: ROBERT KAY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 805 FSL 1949 FEL FEL Bottom Hole: FNL/FSL 805 FSL 1949 FEL FEL  
Sec: 22 Twp: 6S Rng: 97W Sec: 22 Twp: 6S Rng: 97W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 7700 ft

18. Distance to nearest property line: 494 ft 19. Distance to nearest well permitted/completed in the same formation: 308

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	510-18	320	SE/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20040106

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
PLEASE SEE ATTACHED MINERAL LEASE MAP # 3.

25. Distance to Nearest Mineral Lease Line: 805 ft 26. Total Acres in Lease: 5165

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	30	20	55	90	100	90	0
SURF	16	9+5/8	36	2,000	1,000	2,000	0
3RD	8+3/4	4+1/2	11.6	9,129	600	9,129	200

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments I certify that there has been no changes on land use, lease description. The pad has not been built. The pit has not been constructed. The location will require surface disturbance of the pad. The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii). The location is not in a wildlife restricted surface occupancy area. This location is not in a wildlife sensitive habitat area. No rig on site. The production cement top will be 200' above the top of gas. Oxy owns surface and Chevron owns minerals.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JANNI KEIDEL

Title: PERMITTING AGENT Date: 2/11/2010 Email: jek@bry.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 4/9/2010

Permit Number: \_\_\_\_\_ Expiration Date: 4/8/2012

**API NUMBER**

05 045 19298 00

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)24 HOUR SPUD NOTICE REQUIRED. E-MAIL: Shaun.Kellerby@state.co.us 2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE 3)CEMENT TOP VERIFICATION BY CBL REQUIRED. 4)COMPLY WITH ALL PROVISIONS OF THE JUNE 12, 2008 NOTICE TO OPERATORS DRILLING WELLS WITHIN 3/4 MILE OF THE RIM OF THE ROAN PLATEAU IN GARFIELD COUNTY - PIT DESIGN, CONSTRUCTION AND MONITORING REQUIREMENTS. SEE ATTACHED NOTICE. 5)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 36 FEET DEEP.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400037695	DEVIATED DRILLING PLAN	LF@2427763 400037695
400037696	WELL LOCATION PLAT	LF@2427764 400037696
400037700	TOPO MAP	LF@2427765 400037700
400037702	30 DAY NOTICE LETTER	LF@2427766 400037702
400037705	MINERAL LEASE MAP	LF@2427767 400037705
400037708	SURFACE AGRMT/SURETY	LF@2427769 400037708
400038218	APD ORIG & 1 COPY	LF@2427770 400038218
400039150	FORM 2 SUBMITTED	LF@2427771 400039150

Total Attach: 8 Files