

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:
400042356
Plugging Bond Surety
20090078

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION 4. COGCC Operator Number: 69175

5. Address: PO BOX 26
City: BRIDGEPORT State: WV Zip: 26330

6. Contact Name: Sarah Garrett Phone: (303)860-5803 Fax: (303)860-5838
Email: sgarrett@petd.com

7. Well Name: Wells Ranch Well Number: 10F

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7250

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 10 Twp: 5N Rng: 63W Meridian: 6
Latitude: 40.417260 Longitude: -104.431960

Footage at Surface: 1421 FNL/FSL FNL 155 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4710 13. County: WELD

14. GPS Data:

Date of Measurement: 01/28/2010 PDOP Reading: 6.0 Instrument Operator's Name: Thomas G Carlson

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 14942 ft

18. Distance to nearest property line: 155 ft 19. Distance to nearest well permitted/completed in the same formation: 906 ft

20. **LEASE, SPACING AND POOLING INFORMATION**

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J Sand	JSND		160	GWA
Niobrara Codell	NB-CD	407	160	GWA
Sussex Shannon	SX-SN		160	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: 19990086

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
W2NW4, Section 10, Township 5 North, Range 63 West

25. Distance to Nearest Mineral Lease Line: 155 ft 26. Total Acres in Lease: 80

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	470	290	470	0
S.C. 1.1	7+7/8	4+1/2	10.5	7,250	150	7,250	5,850
S.C. 1.2	7+7/8	4+1/2	10.5	5,850	300	5,850	2,950

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Conductor casing will not be used. Well will be tied into common tank battery at the existing Wells Ranch 10A location. Proposed spacing unit is E/2NE4, Sec 9, W/2NW4 10. Location is outside the drilling window and is more than 50 feet from an existing well. exceptions granted.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Sarah Garrett

Title: Landman Date: 2/26/2010 Email: sgarrett@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 3/31/2010

API NUMBER	Permit Number: _____	Expiration Date: <u>3/30/2012</u>
05 123 31408 00	CONDITIONS OF APPROVAL, IF ANY:	

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COGCC ENG COA – SME Note surface casing setting depth change from 450' to 470'. Increase cement coverage accordingly and cement to surface. 1) Provide 24 hr notice of spud to Provide 24 hour notice of MIRU to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us. 2. Set surface casing, per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If completed comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log. Restore surface location.

Attachment Check List

Att Doc Num	Name	Doc Description
1725682	SURFACE CASING CHECK	LF@2440218 1725682
400042366	30 DAY NOTICE LETTER	LF@2427858 400042366
400042367	PLAT	LF@2427859 400042367
400042368	TOPO MAP	LF@2427860 400042368
400042369	EXCEPTION LOC WAIVERS	LF@2427861 400042369
400042375	EXCEPTION LOC REQUEST	LF@2427862 400042375
400042376	PROPOSED SPACING UNIT	LF@2427863 400042376
400042377	PROPOSED SPACING UNIT	LF@2427864 400042377
400042378	PROPOSED SPACING UNIT	LF@2427865 400042378
400043517	FORM 2 SUBMITTED	LF@2427866 400043517

Total Attach: 10 Files