

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐
Sidetrack ☐

Document Number:

2096448

Plugging Bond Surety

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: JEVIN CROTEAU Phone: (720)876-5339 Fax: (720)876-6339
Email: JEVIN.CROTEAU@ENCANA.COM

7. Well Name: IONE Well Number: 2-8-4

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8088

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 4 Twp: 2N Rng: 66W Meridian: 6

Latitude: 40.161450 Longitude: -104.783770

Footage at Surface: 590 FNL/FSL FSL 2205 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4927 13. County: WELD

14. GPS Data:

Date of Measurement: 02/04/2010 PDOP Reading: 2.6 Instrument Operator's Name: CRAIG BURKE

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 50 FSL 1320 FEL/FWL FWL Bottom Hole: FNL/FSL 50 FSL 1320 FEL/FWL FWL
Sec: 4 Twp: 2N Rng: 66W Sec: 4 Twp: 2N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 258 ft

18. Distance to nearest property line: 590 ft 19. Distance to nearest well permitted/completed in the same formation: 900 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407	160	GWA
J SAND	JSND	232-23	160	GWA
NIOBRARA	NBRR	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
ALL OF SEC. 2, S2 OF SEC. 4, NE OF SEC. 8 & E2 OF SEC. 10, T2N, R66W

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 1680

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	800	350	800	0
1ST	7+7/8	4+1/2	11.6	8,088	270	8,088	7,063

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. PROPOSED SPACING UNIT IS S/2SW4 SEC4 AND N/2NW4 SEC 9

34. Location ID: 331119

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JEVIN CROTEAU

Title: REGULATORY Date: 2/22/2010 Email: JEVIN.CROTEAU@ENCANA.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 3/31/2010

API NUMBER

05 123 31412 00

Permit Number: _____ Expiration Date: 3/30/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1770099	SURFACE CASING CHECK	LF@2437917 1770099
2096448	APD ORIGINAL	LF@2423786 2096448
2096463	WELL LOCATION PLAT	LF@2423787 2096463
2096464	TOPO MAP	LF@2423788 2096464
2096465	MINERAL LEASE MAP	LF@2423826 2096465
2096466	SURFACE AGRMT/SURETY	LF@2423789 2096466
2096467	30 DAY NOTICE LETTER	LF@2423790 2096467
2096468	DEVIATED DRILLING PLAN	LF@2423791 2096468
2096469	PROPOSED SPACING UNIT	LF@2423792 2096469
400043046	FORM 2 SUBMITTED	LF@2428227 400043046

Total Attach: 10 Files